

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

JULY 1956



VOL. LI. NO. 7

FIFTY-FIRST YEAR OF PUBLICATION

PRICE 1s. 9d.

ANNUAL SUBSCRIPTION 21s., POST FREE. £2-9s in Canada and U.S.A.

LEADING CONTENTS

	PAGE
By-laws Relating to Fire-resistance	417
A Prestressed Dam in Scotland	419
Stresses in Chimneys due to Temperature By Narain V. Hingorani	425
Reservoir with Walls of Novel Shape	435
General Formulæ for Maximum Bending Moments By L. S. Müller	439
Experimental Road in Nottinghamshire	443

No. 584

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

For catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:
CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1.



For over 60 years

this trade mark has stood for speed and
strength in reinforced concrete work.

DRAGON

(Brand)

PORTLAND CEMENT

Supplied by

THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD.
PENARTH, SOUTH WALES

Telephone : Penarth 300

Telegrams : "Cement, Penarth"



...interesting!

PROMETO MOVING FORMS

**for monolithic concrete
construction**

Prometo hydraulically controlled moving forms maximise production rates, minimise labour requirements, and reduce costs considerably. They are invaluable in the construction of multi-storey buildings, silos, water-towers, shaft-linings and other forms of concrete structure.

We have the sole rights for the manufacture and use of Prometo equipment in the United Kingdom. Enquiries are invited from Consulting Engineers, Contractors and Architects for the arrangement of sub-licence agreements for individual jobs or prescribed districts.

★ **A rapid and
highly economical
method of erecting
structures of all kinds.**

**WILLIAM
THORNTON
AND SONS LTD.**

WELLINGTON RD., LIVERPOOL

BUILDING AND CIVIL ENGINEERING CONTRACTORS

NOTICE

CHANGE of ADDRESS

THE
YORKSHIRE HENNEBIQUE
CONTRACTING CO. LTD.

NOW
HENNEBIQUE HOUSE
123 THE MOUNT
YORK

Tele: YORK 54656


BRANCH OFFICES:

30 WINCOLMLEE · HULL · Tele: HULL 33501

1 WEST BELL STREET · DUNDEE · Tele: DUNDEE 6170

ROYDS WORKS · ROYDS LANE · LOWER WORTLEY · LEEDS · 12. Tele: 637891

Silo Construction




Sugar Silos at York

These two storage silos for the British Sugar Corporation rise 110 feet and have a total capacity of 15,000 tons. They are 66 feet in diameter and the walls, which are eight inches thick, are in prestressed concrete. Construction of the silo walls was carried out with sliding shutters lifted at an average rate of $9\frac{1}{4}$ " an hour by 40 hydraulic jacks operated from a central pump. Prestressing was by the Gifford Udall system with 0.276" diameter wires outside the main walls, protected by coating with Gunitite.

*Contractors for every class of
Building and Civil Engineering work
at home and overseas*

JOHN LAING AND SON LIMITED, GREAT BRITAIN
CANADA, UNION OF SOUTH AFRICA, RHODESIA

LAING



POWER BAR CUTTERS

The BRRL.5A model, illustrated above, will meet all requirements for high speed, economy, and simplicity of operation. This high-speed shearing machine will cut mild steel rods up to 2 in. diameter. It is of robust construction yet portable in view of its compact arrangement, and is powered by electric motor and self-tensioning Vee-belt drive. The moving blade is in continuous action and makes 28 cuts per minute; 2-in. diameter bars require one cut only. The static blade is housed in a specially designed seating which spreads the shearing thrust over a wide area, thus reducing wear and considerably lengthening the life of the machine. Let us send you full details.

CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT


Telephone: Chatham 45580. Telegrams: Compelgi, Chatham.

HANDLING precast
concrete on the site
is made easier with

MARION 33M CRANES

The illustration shows MARION 33M CRANES lifting and placing precast concrete columns for a structure in London recently erected by Messrs. Tersons, Ltd.

The MARION 33M has proved to be the most successful crane for lifting and placing precast concrete structural members of all descriptions, with minimum man-power and operating costs, and with great savings in time. It has a radius of 60 ft. and a boom length of 70 ft., and is fitted with a safe-load indicator. Complete technical information, with details of safe-working loads, are available on request.



TWENTIETH CENTURY EQUIPMENT CO. (LONDON) LTD

244 HARROW ROAD, LONDON, W.3

TELEPHONE: CUNNINGHAM 0291

*For faster placing
and better concrete
use the*



HUMDINGER

IMMERSION VIBRATOR

AVAILABLE WITH GRINDING ATTACHMENTS



Here is an immersion vibrator that will cut your concrete-placing costs in a half-dozen ways. High vibrating frequencies of up to 12,000 r.p.m. give stronger concrete and speed up placing—and you can strike shuttering sooner. At the same time, the 'Humdinger' flexible shafts operate at QUARTER SPEED.

And this means longer life and less maintenance—the drives just keep on running week after week.


Plant records prove that contractors and civil engineers are changing to 'Humdinger' after seeing the difference they can make in concrete placing. Prove it for yourself by using one on your next vibrating job. You can have a 'Humdinger' on trial or hire (with option).




PETROL AND ELECTRIC MODELS AVAILABLE

ACE MACHINERY LIMITED

VIBRATOR DEPT., PORDEN ROAD, BRIXTON, LONDON, S.W.2 Telephone: BRixton 3293 (9 lines)

Buy  and you buy **RELIABILITY**




PETER LIND & CO LTD

ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1

TELEPHONE, ABBEY 7361

FEBCRETE

air entrained concrete



There is indisputable evidence that "Febcrete" Air Entraining Agent provides an easy means of producing better concrete with all-round savings in cement requirements and concrete-placing costs which are far greater than the infinitesimal cost of "Febcrete." This evidence, which is based on the use of "Febcrete" on important concrete constructional undertakings throughout the world, is available without obligation to all Engineers and Contractors.

FEB (GREAT BRITAIN) LTD.

LONDON: 102 KENSINGTON HIGH STREET, W.

MANCHESTER: ALBANY WORKS, ALBANY ROAD, CHORLTON-CUM-HARDY

Telephone: Western 0444

Telephone: Chorlton 1063



On Home and Oversea sites, in single units or in big fleets, specialist-built Thwaites Dumpers (ranging from 15 cwt. to 30 cwt.), with low-ratio gearboxes, cushion-drive transmissions, large skips balanced over the front axle, unique stability and speed, enabling the non-spill carrying of wet loads over the roughest ground, are reducing handling costs and maintaining a reputation of first-class value for money. Every dumper is backed by round-the-corner service after sales.

Write us for demonstration without obligation.

The Thwaites Agricultural Engineering Co. Ltd.
Welsh Road Works, Cubbington, Leamington Spa

Telephone: LEAMINGTON SPA 3089/90.

THWAITES DIESEL DUMPERS on active service to reduce handling costs



'TUSKER'

1½ cu. yd. dumper



**PIN YOUR FAITH
TO THE TESTED
BRAND.**

THIS LABEL ON
EVERY BARREL
CARRIES WITH IT
FIFTY YEARS'
EXPERIENCE OF
MANUFACTURE.

NONE OTHER IS
"JUST AS GOOD"


THE LEEDS OIL & GREASE CO.

Phone 22480

LEEDS, 10

'Grams: "Grease."

**APPROVED
FOR SITE TESTING**
on all Government Departments' Contracts



4" PRESS AND MOULD

6" PRESS AND MOULD

in use all over the world

**MILBANK-WELLS HYDRAULIC PRESS AND CUBE MOULDS
FOR CONCRETE TESTING**

Presses and Moulds in the 2 sizes for Testing 4 in. and 6 in. cubes
up to 16,000 lb. per square inch, complying with B.S. 1881.

MILBANK FLOORS LTD.

PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX.

Telephone: Earls Colne 410

Manufactured for us by Horner & Wells, Ltd., Engineers, Chelmsford, Essex.

BUCKLESBURY HOUSE TO STAND ON 3,500 BORED PILES



This is the site on which the Temple of Mithras was discovered.



This important Office Building in the City of London, 17 storeys high including the basement floors, is supported on Cementation Bored Piles. Approximately 3,500 were constructed well within the contract time despite the fact that delays were unavoidably occasioned by the deliberations on the fate of the Mithras Temple discovered on the site and other major difficulties inevitable on such a large site.

The construction of a surrounding wall to retain the adjoining Queen Victoria Street, Cannon Street and Bucklersbury, was greatly facilitated by the use of our bored piles.

The close proximity of important buildings, including the Mansion House and services such as the Underground Railway, made it necessary to reduce noise, vibration, etc., to an absolute minimum.

The **CEMENTATION**
COMPANY LIMITED

London Office : 39, Victoria St., S.W.1. Tel : ABBey 5726.

BENTLEY WORKS, DONCASTER. Telephone : Doncaster 54177-8-9

Dowsett chose British Ropes wire



... for use in the construction of this engineering shop erected by Dow-Mac (Products) Ltd., for Brooke Marine Ltd. at South Shipyard, Lowestoft. The shop itself is 360 ft. long by 150 ft. wide with a clear height at centre of 41 ft. 6 ins. The structure is entirely of concrete.

WIRE for prestressed concrete

We were among the first producers of wire designed for prestressed concrete work and our wire is in constant demand for use in important constructional undertakings, at home and overseas.



BRITISH ROPES LIMITED, HEAD OFFICE: DONCASTER TELEPHONE: DONCASTER 4010



Water Purification Works constructed in reinforced concrete for the South Staffordshire Waterworks Company. Mr. R. A. Robertson, B.Sc., M.I.C.E., Engineer of the Company.
Reinforced Concrete Designer: Mr. H. C. Ritchie, M.I.C.E.

THOMAS

LOWE


& SONS LTD

Contractors for Reinforced Concrete and Public Works

HEAD OFFICE: CURZON STREET, BURTON-ON-TRENT


TELEPHONE: 4741-2-3

and at Broadway Chambers, Hammersmith, London, W.6. Telephone: Riverside 5234-5-6
and Grenville Buildings, Cherry Street, Birmingham. Telephone: Midland 1500.



C. H. JOHNSON (MACHINERY) LTD
NOW OFFER A COMPLETE RANGE OF

PEINER
TOWER CRANES




The bogie undercarriage makes negotiations of curves possible down to a radius equal to the rail gauge.



Peiner Cranes can be towed from site to site without dismantling.



No rope installation is necessary on site, as all ropes are left in position on crane during transport.



Peiner Tower Cranes have established a world-wide reputation for speed of erection, stability and adaptability. No auxiliary winding or lifting gear is required to erect them, a slewing gear can be steered at the back when on tow to facilitate road transport, while heavy pneumatic tyres protect the structure from shock.

Full details from Sole Agents for Great Britain and Northern Ireland

C. H. JOHNSON (MACHINERY) LTD · ADSWOOD · STOCKPORT · CHESHIRE

Telephone : STOCKport 2642/5.

Telegrams : "Machinery" Stockport.



CHRISTIANI & NIELSEN LTD.

CIVIL ENGINEERING CONTRACTORS



INTAKE TOWERS FOR BRITISH OIL AND CAKE MILLS, ERITH
CONSULTING ENGINEERS: MESSRS. FREDERICK SNOW & PARTNERS

ROMNEY HOUSE, TUFTON STREET, WESTMINSTER, LONDON, S.W.1

Telephone: ABBey 6614/7. Telegrams: Reconcret, Sowest, London. Telex: Reconcret, 2-2305

BUILDERS PLANT

...you've
got to
hand
it to
MILLS

FOR SAFETY, SERVICE AND SATISFACTION

MILLS SCAFFOLD CO. LTD. (A Subsidiary of Guest, Keen & Nettlefolds Ltd.)

Head Office: TRUSSLEY WORKS, HAMMERSMITH GROVE, LONDON, W.6. RIVERSIDE 3011 (10 lines)

Agents and Depots:

BELFAST · BIRMINGHAM · BOURNEMOUTH · BRADFORD · BRIGHTON · BRISTOL · CANTERBURY
CARDIFF · COVENTRY · CROYDON · DUBLIN · GLASGOW · HULL · ILFORD · LIVERPOOL
LOWESTOFT · MANCHESTER · MIDDLESBROUGH · NEWCASTLE · NORWICH · PLYMOUTH
PORTSMOUTH · PRESTON · READING · SHIPLEY · SOUTHAMPTON · SWANSEA · YARMOUTH



1934

Water Tower for Hitchin R.D.C. at Weston,
near Letchworth.



1956

Water Tower for Thorne R.D.C. at Sykehouse,
near Doncaster.



P. P. TAYLOR

(DONCASTER) LIMITED

**BUILDING AND
CIVIL ENGINEERING CONTRACTORS**

6 SOUTH PARADE

DONCASTER

TELEPHONE : 2473-4

EVODE

**SOLVES PROBLEMS OF
COOLING TOWER
INTERNAL SURFACE
PROTECTION**

**EVEN DIRECT TO
GREEN CONCRETE**

The combination of EVODE Insulating Paste and EVODE Black 505 has proved ideal for the internal surface protection of cooling towers, and leading consultants are now adopting this specification . . . "A brush coat with EVODE Insulating Paste I at the rate of $\frac{1}{2}$ lb. per yard super, followed by a coat by brush or spray, of EVODE Black 505 at the rate of 1 gallon to every 40 yards super." This treatment has these supreme advantages — it can be applied to green concrete, i.e. without having to wait at least 28 days before it matures, and to moist surfaces.

EVODE blacks are all true Asphaltic Bituminous Paints

that give better protection . . . the complete range includes:—

505 General purpose coating for iron, concrete, brickwork, glass, etc. Well suited for brushing, dipping and spraying.

505S Heavily bodied bituminous paint for use under extreme conditions of corrosion, particularly suitable for structural steelwork, etc., corrugated iron sheeting. A.I.D. and M.O.S. approved.


505D For the inside protection of drinking water containers of iron and concrete. Quick drying, tasteless and odourless when dry. M.O.W. approved.

505H Thoroughly heatproof (dry heat up to 450°F.) for chimney stacks, etc. Hot water resisting. For the inside and outside protection of hot water tanks.

505W As 505 but suitable for dew-moist surfaces.

505SW As 505S but suitable for dew-moist surfaces.

505Ch Chassis Black. Rapid drying solution for application by spray or brush to all motor chassis.




AN
EVODE
PRODUCT

EVODE LTD - STAFFORD - ENGLAND

Tel: 1 590/1/2 Grams: Evode, Stafford. LONDON OFFICE: 1 Victoria St. S.W.1. Tel: Abbey 4622/3

The Best **BIG** British **BAR BENDER** DIESEL OR ELECTRIC



Bending a single heavy bar



Bending a group of heavy bars to a large radius



Bending a group of small bars to a small radius

For the fastest and most accurate bending of single bars up to 2-inch diameter or a group of bars of combined cross-sectional area of 3 sq. inches, this machine, available with diesel engine or electric motor, has a world-wide reputation.

*** FOR SALE OR HIRE**

ACROW

Send for full descriptive brochure, prices and hire rates to :—

ACROW (ENGINEERS) LTD., SOUTH WHARF, PADDINGTON, LONDON, W.2

Tel: AMBassador 3456 (20 lines)

Branches at: Birmingham · Liverpool · Manchester · Leeds · Bristol · Newcastle · Southampton
Swansea · Glasgow





WATER TOWER AND TANKS, SCUNTHORPE, FOR
APPLEBY-FRODINGHAM STEEL COMPANY

HOLST

& CO LTD

Civil Engineering Contractors, Reinforced Concrete

Head Office: 46 CLARENDON ROAD, WATFORD

WHARF AND TRANSIT SHED, MILFORD HAVEN,
FOR MILFORD DOCKS COMPANY

Messrs. LIVESEY & HENDERSON,
Consulting Engineers.



CONCRETE TAKES COURAGE



Bottling Hall,

Alton

Courage & Co., Ltd., Brewers of London and Alton, have for many years regularly specified Lillington's No. 1 for mixing in concrete to ensure their floors have hard, waterproof and dustless surfaces.

LILLINGTON'S No. 1 METALLIC LIQUID waterproofs cement renderings to walls and basements, and makes concrete floors extremely hard and dustless. The concrete in retaining walls, foundations, flat roofs, and tanks is made thoroughly waterproof, and the setting time of the concrete is accelerated. Architects specify Lillington's No. 1 Metallic Liquid because it is SOLD UNDER GUARANTEE, it is low in cost, and has nearly 50 years' reputation for efficiency

From
5/-
per Gallon

Lillington's
NO. 1 METALLIC LIQUID

Special Prices
for Large
Contracts

WRITE FOR BOOKLET 56 GIVING FULL DETAILS.

GEORGE LILLINGTON & CO. LTD.

WILLOW LANE, MITCHAM, SURREY

Telephone: MITcham 1066

AND IN SCOTLAND: 42 HIGH STREET, GREENOCK

Everyone knows...



... On the stage a fine performance is obvious, but the invisible part of the team behind the scenes is essential to produce the entertainment. In a similar manner the character of the theatre is given by the plastics decorations with their invisible but essential foundation of expanded metal making the theatre the attractive place it is. The Midland Expanded Metal Co. have the ability and specialised knowledge to produce the very best material for this and many other constructional uses.



● Some of the Wakefield enterprises : Steel Copper and Aluminium Wire, Electrical Conductors, Welded Wire Mesh for reinforced concrete, Expanded Metal.

THE SPENCER WIRE COMPANY LIMITED, WAKEFIELD

Telephone : Wakefield 6111 (10 lines)

Telegrams : Spencer, Telex, Wakefield.

Telex No. 55,200

**factory-made
TIMBER & PLYWOOD
SHUTTERING
AND MOULDS
ready for immediate use**

for the erection of reinforced concrete structures of all descriptions, and for the production of precast concrete of all sizes in any part of the country.

**MAY & BUTCHER
LIMITED**


HEYBRIDGE BASIN, MALDON, ESSEX

Telephone: Maldon 698-699.



We supplied factory-made shuttering for use on this circular water tower, recently constructed by Shellabear Price Contractors, Ltd. Formwork Consultant: C. Parry, M.I.C.E., M.I.Struct.E.

"CAPCO" H. F. VIBRATOR



for compacting mortar cubes for Compression Test B.S. 12/1947, B.S. 915/1947, B.S. 146/1947, B.S. 1370/1947. New type automatic control—optional. The vibrator illustrated in the B.S. was built in our works.

The "CAPCO" range of concrete testing apparatus also includes Cube Moulds; Slump Cones; Tensile, Vicat, and Cylindrical Moulds; Tile Abrasion Machines; Compacting Factor Apparatus.

Full details on request.


CAPCO (SALES), LTD.

BEACONSFIELD ROAD, LONDON, N.W.10

Telephone: WILLEDEN 0067-8

(Sole Agents for all "Capco" Products)

Cables: CAPLINKO, LONDON



The bigger the project, the wiser it is to let Wates build. For Wates' system of close architect-owner-builder collaboration pays big dividends. Pre-planning solves *in advance* the problems that can cause delay and extra expense. Pre-planning gives you your building on time, without fuss, and within your budget.

Ideas become concrete when

WATES BUILD

WATES LTD *Building & Civil Engineering Contractors*

HEAD OFFICES · 1258/1260 LONDON ROAD · S.W.16 · Telephone: POLlards 5000
LONDON DUBLIN NEW YORK

GLASCRETE

•
VARIABLE
GRID
WINDOWat
Willenhall
Comprehensive
School, Staffs.
•A. C. H. Seftman, Esq., F.R.I.B.A.
County Education Architect

Reinforced Concrete and Glass

BY

J. A. KING & Co. LTD. 181 Queen Victoria Street, E.C.4
Telephone: CENTRAL 5866 (5 lines)

COPPER STRIPS

for expansion joints


All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.

**ALEX J. CHEETHAM LTD.**

MORTON STREET • FAIRFORTH • MANCHESTER

Telephone: FAIRFORTH 1115/6

DS14



JOHN LEWIS, OXFORD STREET, LONDON

Work on underpinning and foundations, which go down to a depth of 40 feet below Oxford Street, London, was carried on by night and day to speed the completion of this important new building. The timbering was designed to permit reinforcement to be placed with 3" cover from the vertical face of the excavation.


Architects: Slater, Uren & Pike, F/R.I.B.A., 29 Gower Street, London, W.1

Engineers: Hurst, Peirce & Malcolm, M/M.I.C.E., M/M.I.Struct.E.

RUSH & TOMPKINS LTD.

Building and Civil Engineering Contractors

SIDCUP · LONDON · DURBAN · COLOMBO · EDMONTON, ALBERTA



Troublesome curves?

The quickest cure for curve troubles is to contact Ford. They've a pretty range of curves—performance, torque, fuel and B.H.P. covering Petrol and Vaporising Oil Engines from 12 to 58 B.H.P. (Diesel 23 to 52 B.H.P.). Ask to see this satisfying set of curves and specifications. No need to ask about famous World-wide Ford Service . . . but whenever there's a question of curves . . .

— ask the fellows at **FORD**

All enquiries, please, to Dept. I.E.

INDUSTRIAL UNIT SALES DEPARTMENT · FORD MOTOR COMPANY LIMITED · DAGENHAM · ESSEX

TRUCK-MIXED CONCRETE

can be economically
used for all
contracts
in this
area



It is easier, cheaper, and more speedy to use Truck-Mixed Concrete for contracts in the area shown above. We can cater for all Truck-Mixed Concrete requirements, and can supply a material graded to specification with a guaranteed delivery service. For full details send to :

TRENT GRAVELS LTD.

ATTENBOROUGH, NOTTS.

AND KING JOHN CHAMBERS, BRIDLESMITH GATE, NOTTINGHAM.

TELEPHONE: BEESTON 25-4255/6

TELEPHONE: 40557

IBECO

IBECO is a high-quality, tough-textured Kraft paper, waterproof throughout its substance. Used as an undercarpet, it completely prevents unwanted drainage from the mix, safeguards metal reinforcements from deleterious subsoil acids. It bulks small for easy transport, easy storage. It is light in weight, simple to lay, and retains its waterproofness even with rough handling. Makes an excellent curing overlay as well. Write to us for samples and current prices.


THE TRAFFIC ROLLS...
 a steadily increasing load for the country's roads... only concrete soundly founded can stand up to it. That's why, on more and more road repair and construction jobs, you'll see more and more **IBECO** being used. It's absolute impermeability is the soundest insurance of lasting strength where concrete is laid on porous subsoil. It speeds the work, too, and lowers its cost. Keep it in mind for jobs to come!

HILTON GRAVEL

SEVEN
PITS

250
LORRIES

8,000
TONS
PER DAY



FOR QUALITY & SERVICE

REGULAR DELIVERIES THROUGHOUT

STAFFORDSHIRE	•	CHESHIRE
DERBYSHIRE	•	NOTTINGHAMSHIRE
WEST RIDING	•	LANCASHIRE
SHROPSHIRE	•	WARWICKSHIRE
LEICESTERSHIRE	•	RUTLAND

READY
MIXED
CONCRETE

20 miles radius
MANCHESTER

From our Plant
at
RICE STREET
MANCHESTER 3
DEAnsgate 5455

The illustration above shows one of our seven pits equipped with the most modern washing and grading plant for producing concrete aggregates that will satisfy the most exacting requirements for cleanliness and grading to specifications.

HILTON GRAVEL LIMITED

HEAD OFFICE: HILTON DERBY Tel: ETWALL 422



Reinforcement

½" mesh reinforcement in hoppers of coalbunkers at new factory for Associated Weavers Ltd., Tofshaw, Bradford, Yorks.

ONLY EXPAMET EXPANDED STEEL can claim sixty successful years as a steel sheet reinforcement for concrete. Today, Expanded Steel is widely used for all types of civil and structural engineering – buildings, tanks, reservoirs, swimming baths, sea defences and other reinforced concrete construction work. There is a wide range of standard variations and weights in 'Expamet' Expanded Steel Reinforcement. Our engineer can discuss your problems and prepare designs and estimates.

DESIGN SERVICE

A complete concrete reinforcement design service is operated by Expamet to help you. Take advantage of it. Briefly, the service includes: 1. Design with economy; 2. Preparation of working drawings; 3. Supply of reinforcements; 4. Delivery on schedule; 5. Technical advice and literature.

BOLT BOXES

Expamet Foundation Bolt Boxes are manufactured from ½" mesh Expanded Metal, which has the property of being able to retain wet concrete. The Boxes are made conical, cylindrical or rectangular, to suit particular requirements, in any reasonable dimensions.



Expamet

Expanded Metal Products

THE EXPANDED METAL COMPANY LTD.

8 Burwood House, Caxton Street, London, S.W.1.

Tel: ABBey 7766

P.O. Box 14, Stranton Works, West Hartlepool.

Tel: Hartlepool 5531


Also at: ABERDEEN • BELFAST • BIRMINGHAM • CARDIFF • DUBLIN • EXETER
GLASGOW • LEEDS • MANCHESTER • PETERBOROUGH

"SHOCKCRETE"

precast concrete tunnel segments

GLOUCESTER MAIN DRAINAGE

The 9-ft. diameter tunnel for this scheme is 7,868 ft. long, and is lined with SHOCKCRETE precast concrete segments, each 2 ft. wide and about 5 ft. 3 in. long.



WE ALSO SPECIALISE IN

the design and manufacture of all types of prestressed precast concrete structural units, and all other forms of cast stone and precast concrete, including piles, hollow and solid floor units, facing slabs, and other units for building and civil engineering.

SHOCKCRETE PRODUCTS, LTD., RYE HOUSE WORKS, HODDESDON, HERTS.

Telephone: Hoddesdon 3037-8 and 2557

The PC3 Electrically Driven Concrete Pump—20/24 cu. yds. per hour.
 Smaller PC4—8/10 cu. yds. per hour.
 Range up to 135 ft. vertical or 1,500 ft. horizontal.

FOR SALE AND HIRE

EFFICIENT RECONDITIONING SERVICE



CONCRETE BY PUMP AND PIPELINE

- The latest and most efficient method of placing concrete.
- Life of Pump practically indefinite: all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF

PUMPCRET

THE CONCRETE PUMP COMPANY LIMITED

THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546

Telegrams: Pumpcret, Kens, London



a perfect roof...

by

**JOHN MOWLEM
& CO. LTD**

Span 40 feet, length 120 feet, radius 30 feet . . . and its finish is faultless! How was this achieved? By the use of Thamesply Plywood Shuttering, the smoothest, lightest, most economical shuttering of all.

Contractor: John Mowlem & Co. Ltd. for the Telegraph Construction and Maintenance Co. Ltd., Metals Division, Manor Royal, Crawley.
Architect: The late Arthur H. Russell Esq., A.R.I.B.A.

the result of



PLYWOOD SHUTTERING

(Phenol Bonded "W.B.P." Test)
W.B.P. means Weather and Soil Proof

Supplied only through the usual trade channels


THAMES PLYWOOD MANUFACTURERS LIMITED

Harts Lane • Barking • Essex • Telephone: Rippleway 5511

LENSCRETE

GLASS AND FERRO-CONCRETE

for
**SHELL
ROOF**
CONSTRUCTION



LENSCRETE LTD.

66 QUEEN'S CIRCUS

LONDON, S.W.8

TELEPHONE : MACAULAY 1063

Agents in all parts
of the British Isles,
Dominions and Colonies.

GUNITE SPECIALISTS

**W.M. MULCASTER
& CO. (CONTRACTORS) LTD.**

We invite inquiries for Gunite Linings and Renderings
for new or old structures of every kind in any part
of the country.

HASLINGTON

CREWE

Telephone : Crewe 2265-6.

FOR BETTER CONCRETE

LISSAPOL N

—a stable surface-active agent which increases the workability of concrete without significantly affecting its strength. LISSAPOL N can be used:

either to reduce the water content of the mix without affecting workability, thus giving stronger concrete
or to reduce costs by allowing leaner mixes to be used without affecting the strength or workability.

Used on major projects throughout the world.

APHROSOL FC

a powerful, economical foaming agent, for producing aerated concrete in a wide range of densities, suitable for building blocks, roof and floor screeds, etc.

Better thermal insulation

Easy handling

Reduced labour costs



© 1952

Full technical data on request:

**IMPERIAL CHEMICAL INDUSTRIES LTD.,
LONDON, S.W.1.**


THE NEW GANDY BRIDGE FLORIDA

USES THE
LEE-McCALL
SYSTEM

Designed by Florida State Road Department to convert the existing toll bridge between Tampa and St. Petersburg, Florida, into a dual carriageway.

The new bridge, comprising 252—prestressed concrete spans of 48-ft. and 20 spans of 72-ft. with a total length of 13,770-ft. is being constructed by the Hardaway Contracting Co. of Columbus, Georgia.

The prestressing steel for this contract was supplied by Stressteel Corporation, Wilkes-Barre, Pennsylvania who are the licensees of the Lee-McCall System in the United States.



McCALLS MACALLOY LIMITED
TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41


Telephone : ROTHERHAM 2076 (P.B. EX. 8 LINES) • LONDON OFFICE : 8-10 GROSVENOR GARDENS, S.W.1
also at Birmingham and Portsmouth.

Telephone : SLOANE 0420


NO OTHER CEMENT GIVES YOU THIS TIME/STRENGTH ADVANTAGE

Only Aluminous Cement will provide concrete which reduces waiting time to such a low minimum. By careful planning, maintenance work, such as floor repairs, or the installation of new machines, can be accomplished over the week-end, or even over-night, without interruption of production. Keep a stock of Ciment Fondu—against these urgent repairs.

**Concrete for
any purpose
in 24 hours**



Ready to walk upon at
eight hours.



Machinery can be
erected upon founda-
tions at 16 hours.



Road repairs can be
re-opened to traffic at
18 hours.



Piles can be driven at
24 hours.



Write for copy of interesting leaflet :—

"DO THAT CONCRETING JOB OVER THE WEEK-END"

LAFARGE ALUMINOUS CEMENT COMPANY LIMITED

73 BROOK STREET, LONDON, W.1. Tel.: MAYFAIR 8546

AP3/1325

DUCTEX**LIGHTWEIGHT
METAL SHEATH****Specially designed for
forming ducts in
prestressed concrete**


It is available in 10-ft. lengths with screw or bell ends, with internal diameters of $1\frac{1}{2}$ ", $1\frac{3}{4}$ ", 2".

Each length is simply threaded on the cable and screwed or butted into the preceding length. The joins are covered with tape for added protection against the concrete grout entering the duct. The whole cable encased in steel is then placed in the structure in the design position.

After the cable has been inserted, DUCTEX can be bent to the following radii— $1\frac{1}{2}$ " dia. to 10 ft. approx., $1\frac{3}{4}$ " dia. to 12½ ft. approx., and 2" dia. to 15 ft. approx.

DUCTUBE COMPANY LIMITED

1, ADELAIDE STREET · STRAND · LONDON · WC2
Telephone: COVent Garden 1156-7-8



THIS IS AN ACTUAL PHOTOGRAPH
(REDUCED) OF 2" DUCTIFLEX

DUCTIFLEX

THE FLEXIBLE METHOD OF FORMING

**STRAIGHT OR
CATENARY DUCTS**


IN PRESTRESSED CONCRETE

AVAILABLE IN 1½" AND 2"
DIAMETERS, IN 80 FT. COILS
SEND FOR PRICES AND SAMPLES

DUCTUBE COMPANY LIMITED

1, ADELAIDE STREET · STRAND · LONDON · WC2

Telephone : COVent Garden 1156-7-8



The **BISON** plank floor

combines all the structural advantages of in-situ systems with those provided by precast work at lower cost. The plank is factory-made by a method ensuring absolute accuracy of placing of reinforcement. It can be economically combined with any form of construction such as steel or R.C. frames. It is extremely shallow and gives maximum strength/weight ratios.

Shuttering is eliminated. There is only one type of unit to handle. The soffit is level. Construction is quick. The floor can be laid by our erection teams—up to 500 sq. yds. per gang per day—or the planks can be supplied for the contractor to fix.

Trimming for openings in the floor may be carried out within the structural thickness.





CONCRETE LIMITED

Originators of Prestressed Floors in 1948


LONDON Green Lane, Hounslow, Middlesex. Hounslow 2323
LEEDS Stourton, Leeds, 10. Leeds 75421
LICHFIELD Dovehouse Fields, Lichfield, Staffs. Lichfield 2404
FALKIRK Etna Road, Falkirk. Falkirk 1930

STONE COVERING PAINT

WHAT IT IS - AND HOW TO APPLY IT



STONE COVERING—Fine Stipple



STONE COVERING—Coarse Stipple

You will find this booklet very useful. It describes the complete range of Stic B Products, their application and use by the Architect and Builder. Included also is a comprehensive report by the Building Research Station on the conditions under which our products were tested, and the impressive results that were achieved. Please write to our London office, when a copy will be sent you by return.

STIC B PAINT SALES LTD.

99 WANDSWORTH ROAD, VAUXHALL, LONDON, S.W.8

Telephone: RELiance 5566

Output increased by two-thirds!

This machine is specifically designed for the mass production of SOLID blocks in sizes $18" \times 9" \times 2"$, $2\frac{1}{2}"$, $3"$ and $4"$ in thickness and is capable of making 550 units per hour by means of "Duplex" fitments.

Fitments as extras are also available for manufacturing HOLLOW blocks one at a time, having two cavities to standard measurements $18" \times 9" \times 3"$, $4\frac{1}{2}"$, $4\frac{3}{4}"$, $6"$, $8\frac{1}{2}"$ and $9"$ in width.

It is fitted with a large hopper and mechanically operated conveying gear, combined with a feeding box. The gear mechanism is automatically lubricated by an oil bath within the gear box.


Full specification will be sent on application.

TRIANCO LIMITED

IMBER COURT, EAST MOLESEY, SURREY

Telephone : EMBerbrook 3300.

Telegrams : Trianco, East Molesey.



TRIANCO K2. Mark 2.

Automatic Block-Making Machine.

Deferred payments available

TRIANCO

BLOCK-MAKING MACHINES

**CONCRETE
PROOFING
Co. LTD.**

**GUNITE
SPECIALISTS**

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request.

96, Victoria Street, Westminster, S.W.1

Telephone :
VICTORIA 7877 and 6275

Steel Reinforcement

... bent ... bundled ... labelled

Delivered to site ready for fixing •

No loss of time in checking and sort-

ing material • No loss of material

due to prolonged storage on site •

A complete service of
DESIGN, FABRICATION AND FIXING
for all types of Reinforced Concrete
Construction.

T. C. JONES

AND COMPANY LIMITED

REINFORCEMENT ENGINEERS

HEAD OFFICE: WOOD LANE, LONDON, W.12

Telephone: SHEpherds Bush 2020

SOUTH WALES OFFICE:

2 PIERHEAD CHAMBERS, BUTE STREET, CARDIFF

Telephone: Cardiff 28786

REINFORCEMENT DEPARTMENT:

17 BUCKINGHAM PALACE GARDENS, LONDON, S.W.1

Telephone: SLOane 5271

WORKS: Shepherds Bush, London. Neasden, Middlesex. Treorchy, Glamorgan

THE
600
GROUP
OF COMPANIES

All reinforcement enquiries please, to: 17 Buckingham Palace Gardens, London, S.W.1

Colcrete PROCESS

MASS COLCRETE DAM

GOGO FALLS NORTH NYANZA, KENYA

Consulting Engineers:
Messrs. Brian Colquhoun & Partners

Commissioning Authorities:
Macalder Nyanza Mines, Ltd
The Colonial Development Corporation

A mass dam at a remote location containing 30,000 cu. yds. of COLCRETE using rock from excavations and site quarry as aggregate.

Construction by 3 ft. lifts of 100 cu. yds. using two sizes of aggregate for voidage reduction and rubble masonry walls as permanent shuttering.

COLCRETE LTD
GUNLANE - STROOD
KENT

Telephone : 78431 - 2 - 3



FOUNDATION GROUTING.



GROUTING PIPES IN LARGE AGGREGATE.




GROUTING, MIXING & DISTRIBUTING PLANT.



SOUTH BANK EXCAVATIONS.

RANALAH

STEEL MOULDS



Sea Defence Mould, shown by kind permission of Brighton County Surveyor.

Solidly constructed Standard Moulds of many types from stock or specially made to your drawings. Speedy and competitive. Kerb, Garden Edging, and Coping Moulds to B.S. 340-1950.

Send for illustrated catalogue of standard moulds. Accurate and very strongly made.

RANALAH

STEEL MOULDS LIMITED

43, DEVONSHIRE PLACE • BRIGHTON • SUSSEX • Tel.: 22191/3

HISTORICAL HYPOTHESIS NUMBER 2

John Loudon MacAdam

got below
the surface
of things

... **by** realizing the importance of a hard,
long wearing surface for the roads of his day if they were to cope
effectively with the ever growing volume of traffic

How glad he would have been to use present day concrete cured with
SISALKRAFT Blankets. Their toughness and ease of handling simplify
and speed up road making, a safeguard against winter frosts and
assured curing in summer heat.

He would have marvelled, too, at the strength of Subsoil grade
SISALKRAFT which takes such good care of the underside of concrete,
reducing sub-grade friction, ensuring maximum
strength and protection from impurities.

SISALKRAFT
ESTD. 1857


J.H. SANKEY & SON. LTD.

ALDWYCH HOUSE, ALDWYCH, LONDON, W.C.2

Sole Distributors for British Sisalkraft Ltd. Phone: HOLborn 6949 (20 lines) Grams: Brickwork, Estrand, London

The reservoir illustrated, of 25 million gallons capacity, is at present under construction by us for the Colne Valley Water Co. In addition to the unusual nature of the external reinforced concrete wall shown in the illustration, necessitating specialised shutter design, the roof of the reservoir is constructed with 10,000 precast prestressed units. Consulting Engineers : John Taylor & Son, assisted by Leslie Turner & Partners who advised on structure design.

SLOPING-WALL CONSTRUCTION FOR A RESERVOIR



JAMES MILLER & PARTNERS LTD.

**SPECIALISTS IN REINFORCED CONCRETE
PRESTRESSED CONCRETE
AND SHELL ROOF CONSTRUCTION**

18 GEORGE STREET, EDINBURGH
SILVERDALE ROAD, HAYES, MIDDLESEX

TELEPHONE : 30241
TELEPHONE : Hayes 3981

H. W. CHAPMAN, LTD.

THE EMBANKMENT, WELLINGBOROUGH, NORTHANTS

CONCRETING PAPER

CONFORMING TO BRITISH STANDARDS

PROMPT DESPATCH SERVICE

SAMPLES ON REQUEST

Telephone : Wellingborough 2214 (6 lines)



DELIVERED DIRECT TO ANY
CONTRACT BY MOTOR LORRY.

Quotations on Application.

Telephone: Paddington 2024 (3 lines).

WASHED

**BALLAST, SAND, SHINGLE &
Crushed Aggregate for Reinforced Concrete.**

WILLIAM BOYER & SONS, LTD.

Sand and Ballast Specialists,

IRONGATE WHARF,

PADDINGTON BASIN, W.

MEMBERS OF B.S. & A.T.A.

BARS for REINFORCEMENT

BARS in sizes from $\frac{7}{8}$ in. to $1\frac{1}{2}$ in. Mild
Steel 28-33 tons Tensile cut to lengths.

BARS bent to schedule.

BARS for prompt delivery to site at com-
petitive prices.

Send your inquiries to

PASHLEY & TRICKETT · LTD.

STOKE STREET, SHEFFIELD, 9. Telephone : 41136-7. Telegrams : "PET" SHEFFIELD, 9



This one-inch head pneumatic immersion vibrator solves all problems in obtaining efficient vibration of thin concrete members and concrete which is congested with reinforcement or prestressing wire. The vibrator will give equal satisfaction for general concrete work, as the 1" dia. head can be interchanged in a few minutes for a more powerful 1½" or 2½" dia. head. The weight of the type AS 30 is only 15 lb. and its frequency is 12,000 r.p.m.

NEEDLE VIBRATOR

with one-inch
diameter head
for concrete
which is congested
with reinforcement
or prestressing wire

Our range of immersion vibrators also includes the Giant pneumatic vibrator with a 4-in. head, the General-Purpose pneumatic vibrator with a 2½-in. head, and the Lightweight electric vibrator with heads ranging from 1½ in. to 3 in. diameters, which is also available with petrol engine.

COMPACTORS ENGINEERING LTD.

65 EFFRA ROAD,

LONDON, S.W.2

TELEPHONE: BRIXTON 4081-3

H. W. CHAPMAN, LTD.

THE EMBANKMENT, WELLINGBOROUGH, NORTHANTS

CONCRETING PAPER

CONFORMING TO BRITISH STANDARDS

PROMPT DESPATCH SERVICE
SAMPLES ON REQUEST

Telephone : Wellingborough 2214 (6 lines)



DELIVERED DIRECT TO ANY
CONTRACT BY MOTOR LORRY.

Quotations on Application.

Telephone: Paddington 2024 (3 lines).

WASHED

**BALLAST, SAND, SHINGLE &
Crushed Aggregate for Reinforced Concrete.**

WILLIAM BOYER & SONS, LTD.

Sand and Ballast Specialists,

**IRONGATE WHARF,
PADDINGTON BASIN, W.**

MEMBERS OF B.S. & A.T.A.

BARS for REINFORCEMENT

BARS in sizes from $\frac{7}{8}$ in. to $1\frac{1}{2}$ in. Mild
Steel 28-33 tons Tensile cut to lengths.

BARS bent to schedule.

BARS for prompt delivery to site at com-
petitive prices.

Send your inquiries to

PASHLEY & TRICKETT · LTD.

STOKE STREET, SHEFFIELD, 9. Telephone : 41136-7. Telegrams : "PET" SHEFFIELD, 9



This one-inch head pneumatic immersion vibrator solves all problems in obtaining efficient vibration of thin concrete members and concrete which is congested with reinforcement or prestressing wire. The vibrator will give equal satisfaction for general concrete work, as the 1" dia. head can be interchanged in a few minutes for a more powerful 1½" or 2½" dia. head. The weight of the type AS 30 is only 15 lb. and its frequency is 12,000 r.p.m.

NEEDLE VIBRATOR

with one-inch
diameter head
for concrete
which is congested
with reinforcement
or prestressing wire

Our range of immersion vibrators also includes the Giant pneumatic vibrator with a 4-in. head, the General-Purpose pneumatic vibrator with a 2½-in. head, and the Lightweight electric vibrator with heads ranging from 1½ in. to 3 in. diameters, which is also available with petrol engine.

COMPACTORS ENGINEERING LTD.

65 EFFRA ROAD,

LONDON, S.W.2

TELEPHONE: BRIXTON 4081-3

use the **A.B.**
SERVICE
for concrete work

SHUTTER PANELS

All sizes and types

ADJUSTABLE SHORES

for floor and beam support

ADJUSTABLE CENTRE FORMS

for floor support

SHUTTERLOCK WALING CLIPS

for bracing with scaffold tube and locking the panels together, eliminating nuts and bolts in shuttering. Tremendous saving in erecting and striking costs

COLUMN CLAMPS : BEAM CLAMPS

ROAD FORMS : TRENCH STRUTS

We also design and manufacture Steel Moulds for Floor Beams, Piles, Railway Sleepers and all other precast concrete products

Let us solve your problems

A. B. MOULD & CONSTRUCTION CO., LTD.

92 WHITEHORSE ROAD

CROYDON

SURREY

Telephone : Thornton Heath 4947.

Telegrams : Abmould, Croydon.

WORKS: VULCAN WAY, NEW ADDINGTON, SURREY

37



**P R E S T R E S S E D
C O N C R E T E U N I T S**

F O R M I N G

T R U N K R O A D B R I D G E

Photograph by
permission of
Lincolnshire
C.C.

A N O T H E R

A N G L I A N

P R E S T R E S S E D P R O D U C T

**P Y L O N S · P I L E S A N D
S H E E T P I L E S · R O A D
A N D R A I L B R I D G E S
R O O F & F L O O R B E A M S**

A N G L I A N B U I L D I N G P R O D U C T S L T D · L E N W A D E 1 5 · N O R W I C H

Tel.
Gt. Witchingham 291

No. 10 IN A SERIES SHOWING RECENT DEVELOPMENTS IN CONCRETE CONSTRUCTION

Prestressed Concrete —a complete alternative to steel

BOWATER'S
MULTIWALL
PAPER SACK FACTORY
ELLESMERE PORT



Ever since prestressed concrete construction was first used in this country, designers, architects and civil engineers have specified "Wire by Johnsons". The reason is quality, built up on early experimental work with those specialist designers who studied and worked on the Continental development of this new building technique.

Johnsons have a long record of "Firsts" including indented wire for greater bonding and coils of 8 ft. diameter, from which the wire pays out straight.

The Sack Factory consists of 16 bays each 100 ft. span by 31 ft. wide of North light barrel vault construction with a shell thickness of 3 in. The Reel Store has 8 barrel vaults 83 ft. long by 25 ft. wide with a shell thickness of 2½ in. *The design aspects of this project and others are published in brochure form. Write for your copy now.

Sponsor: THE BOWATER PAPER CORPORATION LTD., LONDON, W.1.

Architects: FARMER & DARR, F/R.I.B.A., LONDON, S.W.1.

Consulting Engineer: C. V. BLUMFIELD, B.Sc.(Eng.), M.I.C.E., M.I.Struct.E., of WOKING, SURREY.

Contractors: SIR ALFRED MCALPINE & SON, LTD., WIRRAL, CHESHIRE.

wire was essential—

Johnsons the choice!

Richard Johnson & Nephew Ltd., Manchester, 11


Look for the name **ALLAM**
and buy the best
VIBRATING EQUIPMENT
made today

**FLEXIBLE DRIVE
INTERNAL
VIBRATOR**



The most comprehensive range of Allam internal vibrators includes petrol, electric and pneumatic types with frequencies up to 11,500 r.p.m., and all offered with three sizes of interchangeable vibrating units to suit very harsh dry concrete mixes, various cross-sections, and spacing of reinforcement.

External vibrators are offered in five sizes to suit the size and shape of the member to be concreted. They are used as complementary to internal vibrators, or where the section and reinforcement exclude the entry of internal vibrators.



**TRILLOR
ELECTRIC
EXTERNAL
VIBRATOR**

Details of these and other items of contractors' plant sent on request.


E. P. ALLAM & CO. LTD.

LONDON : 45 Great Peter Street, S.W.1.

Telephone : Abbey 6353 (5 lines)

SCOTLAND : 29 Cavendish St., Glasgow, C.S. Tel.: South 0186. Works : Southend-on-Sea. Tel.: Eastwood 55243

WHITEHEAD'S REINFORCING BARS



.....

have been regularly used

.....

by leading Contractors for

.....

reinforced concrete work

.....

since 1903

.....

We were the pioneers in the supply of steel bars for reinforced concrete work and have given to the industry over 50 years of unbroken service, unequalled for quality and dependability. Contracts on which WHITEHEAD STEEL have been used include some of the largest and most important in the country.

We can supply bars bent to shape, hooked, etc.,
in accordance with Contractors' requirements,
at reasonable charges.

THE
WHITEHEAD IRON & STEEL CO. LTD.
NEWPORT Tel. No. NEWPORT 65401 (PBX). MON.


LONDON OFFICE: Steel House, Tothill Street, S.W.1. Telephone: Whitehall 2984.

BIRMINGHAM OFFICE: King Edward House, New Street, 2. Telephone: Midland 0412-3.

MANCHESTER OFFICE: Chronicle Buildings. Telephone: Blackfriars 3172.

GLASGOW OFFICE: 50 Wellington Street, C.2. Telephone: Central 1528.

A COMPREHENSIVE TECHNICAL BROCHURE



**For big savings
in concrete
formwork**

If concrete is your business you will find this latest Rawlplug Company publication of great value and interest. It is packed with practical, down-to-earth information on shuttering problems together with details of Rawlties, Rawloops and Rawlhangers. May we send you a copy? Apply on your letterheading, send business card or state trade or profession.



**THE WORLD'S LARGEST MANUFACTURERS
OF FIXING DEVICES**

It's called a Channelizer



McCall's "MATOBAR" Fabric was used in this traffic "Channelizer" constructed for the Montreal City Planning Department. The junction is at Pie IX Boulevard and Sherbrooke Street East, Montreal P.Q.

*Photograph by courtesy of
"The Gazette"—Montreal*

**McCall's
MATOBAR**

Welded

**FABRIC REINFORCEMENT
FOR ROADS**

REINFORCEMENT



McCALL'S

McCALL & CO. (Sheffield) LTD.

Templeborough

Sheffield

P.O. Box 41

Telephone: ROTHERHAM 2076 (P.B. Ex 8 Lines)

London Office: 8-10 Grosvenor Gardens, S.W.1.

Tel: Sloane 0428



Model VP 350-A (Swivel Base or Barrow Mounting)

Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

*For Greater Strength, Firmer Bonding
and Better Surfacing of Concrete—*

"BAXTUL"

Regd. Trade Mark

British Made

Extra-High Frequency

INTERNAL CONCRETE VIBRATORS

● The model illustrated here operates 9,000 to 15,000 Vibrations per minute from low flexible shaft speeds of 4,500 to 7,500 R.P.M.

● Petrol or Electric Drive.

● Robustly built throughout and backed by genuine service.

● Fitted centrifugal clutch, long-life flexible drive and Vibrator.

This unique machine, with quick-change additional tools, can also be used for : SURFACING, WET-RUBBING CONCRETE, GRINDING, DISC SANDING, AND DRILLING (up to 1½" in Concrete, 1" in Steel, and 2" in Wood)

★ We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world.

30 years' experience in the design and manufacture of flex-shaft tools.

THE FLEXIBLE DRIVE & TOOL CO., LTD.

EDENBRIDGE, KENT. Telephone : 3385-6

LONDON OFFICE : 17 QUEENSBERRY WAY, S.W.7. Telephone : KENSington 3583



THE "JOHN BULL" CONCRETE BREAKER

NEW "B.A.L." TYPE.

INCREASED:—

PENETRATION, RELIABILITY, LIFE.

REDUCED:—

VIBRATION, NOISE AND WEAR.

THESE ARE THE SALIENT FEATURES
OF THE NEW CONCRETE BREAKER

★ ★ ★

REAVELL & CO., LTD.

RANELAGH WORKS, IPSWICH.

TELEGRAMS : "REAVELL, IPSWICH."

TELEPHONE : 2124



THE ABOVE VIEW SHOWS THE WORK IN PROGRESS

the new
DEAL PROMENADE PIER
is being constructed for the
Borough of Deal by

CONCRETE PILING LTD.

10 WESTMINSTER PALACE GARDENS, ARTILLERY ROW, LONDON, S.W.1



Phone : ABBey 1626/7

Consulting Engineers:
Sir Wm. Halcrow & Partners
M.M.J.C.E.

Specialists in the construction of all
forms of reinforced concrete structures
for industrial and public authorities.

High Strain patented Steel Wire for Prestressed Concrete

Manufactured by-



LEE

OF SHEFFIELD

TRUBRITE STEEL WORKS - MEADOW HALL - SHEFFIELD

Tel : Sheffield 36931 (10 lines)

London Office: Stafford House, 40/43 Norfolk St., Strand, W.C. 2. Tel.: Temple Bar 7187
& 7188. Birmingham Office: 191 Corporation St., Birmingham 4. Tel.: Central 6801 & 6802

UNI-TUBES LTD. Enquiries to London Office

9 SOUTH MOLTON STREET, W.1 Telephone: Mayfair 7015

WORKS: ALPHA STREET, SLOUGH Telephone: Slough 25476-8



The pliable steel tube for forming DUCTS in concrete

Ducts for stressed concrete

Labour saving . . . easy to install . . . outer corrugation gives a perfect bond to the surrounding concrete . . . the inside of the tube is smooth to facilitate the passage of bars or cables and allows free flow of grout. These are some of the advantages of the new Uni-Tube which make it the ideal and economical method of forming ducts with unskilled labour and without any special apparatus. The Uni-Tube is left permanently in the concrete. Metal coupler covers for Macalloy couplers, also plain tube connectors and grout-feed connectors can be supplied.

Supplied in $\frac{1}{4}$ ", $\frac{1}{2}$ ", 1", $1\frac{1}{2}$ ", $1\frac{3}{4}$ ", 2 ", $3\frac{1}{2}$ ", and 6" i.d.

As approved and supplied for the Lee-McCall, Freyssinet, and Gifford-Udall systems. Also suitable for other systems and designs.

Ducts for concrete installations

Uni-Tube is also being widely used as the best and the most economical means of providing a duct in concrete which has a smooth bore, through which electrical wiring, piping, etc., can be passed with speed and a saving in labour.

Available in sizes as above or up to $7\frac{1}{2}$ i.d. in alternative grades.

Drum packing containing up to 10,000 ft. protects tubing in transit and ensures easy handling on site. Required lengths cut with a strong knife.

**EXTERNAL RIBS • SMOOTH BORE • EASILY BENT BY HAND
STAYS PUT • EXTREMELY LIGHT WEIGHT • NO DISTORTION
OF BORE • NO FRAYED OR LOOSE ENDS**

Supplied to leading contractors throughout the world

**WATERTIGHT
LININGS
FOR
RESERVOIRS,
SWIMMING
BATHS, ETC.**



**LININGS
FOR
TUNNELS,
SEWERS,
TANKS.**

*Specialists in the Repair and Reconditioning of
Reinforced Concrete Structures, etc.*

THE

GUNITITE
CONSTRUCTION CO. LTD

WESTERN HOUSE, HITCHIN, HERTS.

Telegrams :

Gunite
Hitchin

Telephone :


Hitchin
4371

for laboratory and small scale production

3-TIER BALL MILL

This new ball mill is a useful unit for carrying out a number of separate jobs or for dealing with different quantities at the same time. Arranged with three separate motors and with three pairs of $2\frac{1}{2}$ " diameter rolls in three tiers. Each pair consists of one driven and one idler roll and the latter can be placed in any of three positions to accommodate containers up to 9" diameter.

All three tiers can be operated simultaneously or one or two separately, and provision is made for varying the speed of the driven rolls. Each tier will carry two 1-gallon or three $\frac{1}{2}$ -gallon or four 2-pint or five 1-pint, and various combinations of the different nominal capacities can be operated at the same time.




PASCALL

Write or telephone Crawley 251666 for List BM 5007

THE PASCALL ENGINEERING CO. LTD · GATWICK ROAD · CRAWLEY · SUSSEX



Maxweld reinforces it



All over the world, MAXWELD reinforces it: concrete and brickwork, in roads, locks, factories, docks, bridges, spas and reservoirs. *Do you need reinforcements?* Call up the MAXWELD man! He'll tell you all about MAXWELD fabric — made to BSS 1221 Part A, closely controlled for quality from raw material onwards, available for quick delivery anywhere. He'll tell you what type you need, how much you need, and how much it's going to cost you. He's backed by *Richard Hill's Design Service*, always ready to work out detailed plans and estimates. Call up the MAXWELD man— at Middlesbrough, London, Birmingham, Manchester, Leeds, Bristol and Glasgow.

Maxweld fabric

is manufactured by RICHARD HILL LIMITED (Established 1868)


Newport Wire and Rolling Mills, Middlesbrough, Yorkshire. Tel: Middlesbrough 2206

A MEMBER OF THE FIRTH CLEVELAND GROUP



CIRC 1111

IF IT'S A BENDING JOB...



IT'S A JOB FOR KENNEDY BENDING MACHINES

... featured above is the 12½ Bar bending machine for the accurate and rapid cold bending to precise measurement of mild steel reinforcing bars of up to ½" diam.

For full particulars of all Kennedy benders write to :-

**W. KENNEDY LTD., STATION WORKS,
34 WEST DRAYTON, MIDD. West Drayton 2084**



THE CONCRETE YEAR BOOK

1956 EDITION ∴ NOW READY

PRICE 7s. 6d. 1144 PAGES By Post 8s. 11d.



Gunite & Cementation

Systematic repairs to structures based on systematic diagnosis of defects


WHITLEY MORAN

& CO., LTD

SPECIALISTS IN THE REPAIR OF
ENGINEERING STRUCTURES

5 Old Hall Street · Liverpool 3

Telephone: CENtral 7975



Trent Gravels

10,000 tons per week

Washed & Crushed 1½ in. to ½ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH

NOTTS

Telephone: Beeston 54255.


The new edition of this work of reference, edited by Oscar Faber, C.B.E., D.Sc., M.Inst. C.E., and H. L. Childe, contains more than 1100 pages. It comprises a Handbook for everyday reference, a complete Directory of the concrete industry and a Catalogue illustrating and describing the products of more than 800 firms engaged in or catering for the concrete industry.

Published by

CONCRETE PUBLICATION LTD.,

14 Dartmouth Street, London, S.W.1.

REINFORCED CONCRETE BARS



Reinforced Concrete Bars to BS 785
(Mild, Medium or High Tensile Steels)
Straight or Cut and Bent to Specification
Rounds $\frac{1}{2}$ " Dia. and up
Squares $\frac{1}{2}$ " and up
Deformed or indented bars $\frac{1}{2}$ " up to $1\frac{1}{2}$ "



COLVILLES LTD

FITNESS FOR PURPOSE STEELS

COLVILLES LTD 195 WEST GEORGE ST. GLASGOW C.2

CHEMICAL BUILDING PRODUCTS LIMITED

in the forefront of concrete treatments

CONPLAST

CONCRETE PLASTICISER

for higher strength, greater density
improved workability

PROLAPIN

INTEGRAL LIQUID CEMENT WATERPROOFER

for permanent, indestructible impermeability

LITHURIN

CONCRETE FLOOR TREATMENT

for resistance to wear, permanent dust binding,
proof against acids, oils, slurries, etc.

QUICKSocreTE

RAPID SETTING and HARDENING

for plugging and sealing under water pressure,
controlled setting of mass concrete

FULL INFORMATION AND TECHNICAL SERVICE
AVAILABLE ON REQUEST

WARPLE WORKS · CLEVELAND ROAD
HEMEL HEMPSTEAD · HERTS

Telephone: Boxmoor 4900 (5 lines).

Telegrams: Prolithu Hemel Hempstead

CHEMICAL BUILDING PRODUCTS LIMITED

in the forefront of concrete treatments

CEBEX 124

MULTI-PURPOSE SLURRY LIQUID

for re-surfacing worn concrete floors; effective
bonding of new concrete to old.
Highly adhesive to smooth surfaces;
eliminates hacking for key

CEBEX 113

EXPANDING GROUTING MATERIALS

for heavy machine bedding

CONBEX

EXPANDING PLASTICISING GROUTING MATERIAL

for post-tensioned concrete work

WETEXI 'B'

COLOURLESS WATERPROOFING IMPREGNATION

for treatment of damp walls, etc.

ORKIT and TEKTAM

RANGE OF BITUMINOUS LIQUID and PLASTIC COATINGS

for concrete, steel, etc.

FULL INFORMATION AND TECHNICAL SERVICE
AVAILABLE ON REQUEST

**WARPLE WORKS · CLEVELAND ROAD
HEMEL HEMPSTEAD · HERTS**

Telephone: Boxmoor 4900 (5 lines)

Telegrams: Prolithu Hemel Hempstead



The comprehensive range of the J.D. Series of Spinning Plants and the balanced design of the steel moulds enable you to produce centrifugally spun concrete units of an exceptionally high quality, together with an increased productivity rate and every possible saving in labour requirements and time. They are British designed and built throughout. Send for full technical details



*the most comprehensive
mould service in the world*

The Stelmo Mould Service can also cater for all mould requirements—large or small and to any design. For all-round satisfaction, consult the STELMO MOULD SERVICE.

STELMO, LTD., BETHWIN ROAD, LONDON, S.E.5. Telephone : Rodney 5981

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume LI, No. 7.

LONDON, JULY, 1956.

EDITORIAL NOTES

By-laws Relating to Fire-resistance.

MUCH time and labour have been wasted in some offices due to lack of knowledge of the regulations relating to the fire-resistance of reinforced concrete contained in Model Building By-laws, Series IV, issued by the Ministry of Health in the year 1953. These by-laws * have been adopted by most local authorities in Great Britain, but it is not uncommon for them to receive for approval designs that do not comply with the requirements for fire-resistance. A common result is that a design that is not acceptable is altered when the requirements are known, and, apart from the time wasted in making the alterations, the revised design is seldom as economical as it would have been had the requirements for fire-resistance been complied with in the first place. For example, designs so altered have incorporated slabs that are unnecessarily thick, or the reinforcement has been so closely spaced that the cost of construction has been increased. It is therefore desirable that the by-laws be studied before a design is made. It may be mentioned that Constructional Bye-laws, Schedule IV, of the London County Council are very similar to the Model Bye-Laws of the Ministry of Health.

The regulations on fire-resistance apply to buildings according to their use, their height, their cubic capacity, their floor area, and in certain classes of buildings the distance from the nearest boundary of adjoining property has to be taken into account. Fire-resistance is measured by the period which an element of a building can withstand heat of a certain intensity and under certain conditions as described in British Standard No. 476, "Fire Tests on Building Materials and Structures". The requirements vary from half an hour for domestic buildings less than 75 ft. high and up to 125,000 cu. ft. in capacity to four hours for storage buildings exceeding 75 ft. in height, or 7500 sq. ft. in floor area, or 250,000 cu. ft. in capacity. Also, the requirements for the fire-resistance of walls separating buildings vary from one to six hours, and fire-resisting dividing walls must be able to resist fire for from two to four hours. A further by-law states that any part of a structural frame, or any beam or column carrying an external wall, a wall separating buildings, or a fire-division wall, must have the same resistance to fire as the class of building of which it is a structural member.

In the case of reinforced concrete beams and columns, and floors comprising solid or hollow precast beams or hollow blocks, the by-laws include tables giving

* H.M.S.O. Price 2s. 6d.

the minimum dimensions, thicknesses, and cover of concrete, and it is to be noted that the minimum overall dimensions of free-standing columns are 12 in., 10 in., and 8 in. for fire-resistances of two hours, one hour, and half an hour respectively. However, columns with minimum dimensions of 12 in. and 10 in. are permissible for periods of fire-resistance of four hours and two hours respectively provided that 2-in. mesh reinforcement is placed centrally in the cover to the longitudinal reinforcement. This requires some means of holding the mesh in its correct position. One method is to wire concrete half-washers of the required width to the main longitudinal bars and to wire the mesh to the washers. Other methods may be devised, such as steel washers threaded on to the bars and wired to them at intervals, but these may cause difficulty in placing the concrete in the shutters and in keeping the mesh in position, especially if vibrators are used.

In the case of reinforced concrete beams the least covers of concrete required for fire-resistances of four, two, one, and one-half hours are $2\frac{1}{2}$ in., 2 in., $1\frac{1}{2}$ in., and 1 in. respectively. Thus a beam with a fire-resistance of four hours will have an effective width 5 in. less than its total width, instead of the normal 2 in. (1 in. of cover or twice the diameter of the bar on each side); the effective depth will be probably at least 3 in. less than the overall depth, with the possibility of still further reduction due to the lower bars having to be in two layers because of the increased side cover, with a consequently further reduced carrying-capacity.

In the case of solid slabs the normal $\frac{1}{2}$ in. of cover is sufficient except for a fire-resistance of four hours. The minimum floor thicknesses vary from 3 in. to 6 in., and this also applies to precast beams of U, channel, or tee sections, whereas for hollow-block construction the total thicknesses of combustible material (excluding ceiling finishes) vary from $2\frac{1}{2}$ in. to 5 in.; it is, however, possible to obtain the required thickness by a topping which must, of course, be allowed for in the design. In special cases a certificate may be obtained for a special form of design if the components are submitted to the Fire Research Station for testing. For example, an 8-in. square column has been approved for a fire-resistance of one hour with 2-in. mesh reinforcement in the cover. Steel stanchions and beams must also have a cover of concrete varying with the period of fire-resistance required, although brickwork and fire-resisting materials may in certain cases be used in place of concrete. Also concrete columns protected by brickwork may be smaller in cross section than columns not so protected.

It is seen from the foregoing that the designer must be acquainted with the requirements of the by-laws because they affect the thickness of the concrete cover of beams and slabs and the cross-sectional area of columns. In the fourth schedule of the by-laws various constructional materials are listed and their periods of fire-resistance are given. In the regulations of the London County Council a maximum fire-resistance of four hours only is required for walls separating buildings and the minimum requirements for construction and materials are given in the sixth schedule; this compares with six hours in the fourth schedule of the model by-laws of the Ministry of Health. Also, the London County Council regulations give requirements for the fire-resistance of stairs, doors, and glazing that are not specifically dealt with in the by-laws issued by the Ministry of Health. It should be noted that some materials that are generally regarded as fire-resisting may not satisfy the requirements; for example, asbestos-cement sheets may not be accepted as a wall covering for structures near the boundaries of a site.

A Prestressed Dam in Scotland.

AN unusual use of prestressed concrete is being made in the Allt-na-Lairige dam at present under construction for the North of Scotland Hydro-electric Board. Allt-na-Lairige is a tributary of the river Fyne in Argyll, and the reservoir formed by the dam will impound 800,000,000 gallons of water. The dam is 1360 ft. long and has a maximum height of about 73 ft. The spillway, draw-off sections,

tivity of concrete is usually small and is highly stressed. In a dam, however, where its own weight produces a stabilising force, the most economical design is related to the volume of concrete and the cost of the high-tensile steel bars and anchorages to produce the desired prestressing force. At Lairige this resulted in a cross section in which about 44,000 tons (24,000 cu. yd.) of concrete and




Fig. 1.—Dam during Construction.

and the low terminal blocks have the usual section of gravity dams but the central section, 966 ft. long, is prestressed. Fig. 1 shows the dam during construction and Fig. 2 is a typical cross section.

The saving compared with the usual type of gravity dam is due to the provision of a vertical stabilising force by prestressed bars at about half the cost of obtaining a similar force by a weight of concrete alone, and also this force may be placed in the most effective positions. The thinner section thus achieved produces further economies by reducing the uplifting force, requiring less excavation, and shortening the period of construction.

In prestressed construction the quan-

48,000 tons of vertical prestressing force stabilise the dam. For practical reasons there is a constant prestressing force throughout the full height without intermediate anchorages. This allowed uninterrupted concreting without special scaffolding to support the bars, and all the tensioning was done at the top of the dam after the concrete had been completed.

The criterion for the assumed stresses differs from the usual practice for gravity dams by providing for the full uplifting pressure at the upstream toe and permitting in the lower half of the downstream face a principal tension of 50 lb. per square inch with the reservoir empty.




Fig. 2.—Typical Cross Section.



Fig. 3.—Assembly of Prestressing Bars.

Since all the stresses at the base are low this permitted a considerable increase in the effective lever arm of the steel at the base, with consequent saving in steel. A small amount of mesh reinforcement is provided to prevent cracking due to tensile stresses in the downstream face, and the anchorages at the top and bottom are reinforced to resist tension due to the high bearing-pressure (2500 lb. per square inch) of the anchor-plates.

At the beginning of the work tests were made to determine the depth of anchorage required in the rock and to select a suitable non-bonding wrapping for the prestressing bars. Freyssinet flat jacks were cast in the concrete at the bottom of the

test-pit and a vertical load of 4400 tons was produced.

Method of Construction.

The dam was constructed in blocks 42 ft. long each with two anchorages in the foundation rock at 21 ft. centres. An anchorage was formed by excavating a pit, 4 ft. diameter and about 27 ft. deep, in the granite below the level of the cut-off trench. The bottom of the pit was conical in shape to form the anchorage. In each anchorage there are twenty-eight 1½-in. diameter high-tensile steel bars which were tensioned to 42 tons per square inch and then released to produce a working stress of 37 tons per square inch, resulting in a force of about 1040 tons per anchorage. The twenty-eight bars are anchored at each end by nuts bearing on a single mild steel plate. The bars were arranged to allow access to the centre for erection and concreting in the pits.

The bars were erected in three lifts (Fig. 2). The first two were below the level of the rock and these bars were concreted in the pits and in the foundation of the dam. These bars were covered with tape impregnated with petroleum



Fig. 4.—Prestressing Bars for Third Lift.

grease over which was wrapped bituminous tape for protection during handling and concreting. A group of bars for the first lift is shown in *Fig. 3*. This assembly was lowered by a derrick to the bottom of the pit, and high-quality concrete in the proportions of 1 : 4 was placed in the cone to surround the bars and the anchor-plate. After concreting, the top template was removed and the bars of the second lift were connected. These were then slightly tensioned on a temporary cross-head by tightening the nuts to position and straighten the bars, and the concreting was completed to the level of the drainage channel (*Fig. 2*). Above this level the bars were not covered but were contained in an open shaft measuring 4 ft. by 2 ft. 3 in., which remained open until the tensioning was completed. This shaft starts at the lowest level of the block where it can be drained by gravity.

Concreting was continued to 13 ft. below the top of the dam, the third lift of bars was lowered down the shaft by the derrick, and concrete placed to that level. These bars were suspended from a steel trestle (*Fig. 4*) while being connected to the bars below, and were also slightly tensioned while the next lift of concrete was placed around the bars, which were wrapped to prevent bond. Two more lifts of concrete completed the top anchorage-block and the anchor-plate was then bedded down on 1 : 3 concrete made with granite aggregate. Through the centre of the top anchor-plate there is a duct of 12-in. diameter connecting



Fig. 5.—Tensioning the Bars.

with the shaft 13 ft. below to enable this to be filled with concrete after tensioning the bars.

Except at the end anchorages all the stresses in the concrete are low. At the



Fig. 6.—Downstream Face of Dam.

bottom the concrete is in the proportions of 1 : 4, and 1 : 5 concrete is used in the top. The concrete in the base is in the proportions of 1 : 3½ in the heart and 1 : 5 in the facings. The concrete was placed in lifts of 5 ft. by derricks. Granite aggregate from 2½ in. down was quarried and crushed on the site, proportioned by weight, and mixed in a 1 cu. yd. mixer. The sand obtained from the crushed rock was mixed with an equal quantity of natural sand, and workability was improved by the addition of an air-entraining agent. The concrete in the anchor-pits was placed by a tremie pipe, and a similar arrangement is now being used to place

the concrete in the shafts, in which a very workable mixture in the proportions of 1 : 5½ is used.

The tensioning of the bars at the top anchor-plate is shown in *Fig. 5*, and *Fig. 6* is a general view of the dam with the main concrete work completed. The remaining work is due to be completed soon, and impounding of water will then begin.

The engineers for the project are Messrs. Babbie, Shaw & Morton, of Glasgow, and the contractors are Messrs. Marples, Ridgway & Partners, Ltd., London. The Lee-McCall system of prestressing was used.

A Dome of 165 ft. Diameter.

A DOME over a public building in Japan is described by Professor Yoshikatsu Tsuboi and Mr. Kinji Akino in Vol. 15 of the Proceedings of the Association for Bridge and Structural Engineering.*

The building (*Fig. 1*) has seating accommodation for 1400 people. The radius of the dome is 164 ft. and the rise 22 ft. The height from the ground to the crown is 46 ft. The roof is supported on steel rollers (*Figs. 2 and 3*) on twenty columns. The dome is 4½ in. thick at the centre increasing to 2 ft. 3½ in. at the edge. The floor was concreted after the foundation was completed and on this the centering was built. In the centre the supports were spaced 5 ft. 2 in. radially from the apex, and the spacing was reduced as the load increased.

The reinforcement was very closely spaced at the circumference, and was butt-welded and tested in tension before

use. Blocks of concrete were fixed to the top and bottom bars to ensure the re-



Fig. 2.—Detail of a Roller Bearing.




Fig. 1.—Completed Structure.

* Verlag Leeman, Zürich. Price 38 Swiss francs.




Fig. 3.—Roller Bearing at Circumference.

quired cover. A coarse cement was used in order to reduce cracks due to shrinking. Where the slope was steep, wire mesh was placed on the reinforcement to prevent the concrete sliding. No top shutters were used.

The dome required 733 cu. yd. of concrete. The outer part, containing 490 cu. yd., was cast continuously. Two mixers of 21 cu. ft. capacity were used and concreting was completed in about twenty-three hours. The concrete was compacted by a vibrator in the edge-beam and by hand elsewhere; it was cured with wet

mats for four weeks, when the centering was removed.

The central part of the dome is of uniform thickness and was designed by an approximate method. The paper shows how the equations were derived; these include the effects of temperature, unsymmetrical loading, and openings in the slab. The lower part of the dome was designed as a spherical shell of varying thickness, and the method is explained in detail. The results are compared with those obtained by the general approximate method, assuming a uniform thickness.

Stresses in Chimneys due to Temperature.

By NARAIN V. HINGORANI, B.Eng.

In Combination with Vertical Stresses.

At a section of a chimney the stresses in the concrete and the reinforcement due to the total weight and the wind pressure are first calculated, and the stresses due to the difference in temperature through the thickness of the concrete are then calculated. In the following, equations are derived for combining these stresses, and graphs are given to facilitate the calculations. The following applies to a chimney with reinforcement in the outer face only. The symbols used are :

- d , thickness of the wall.
- nd , distance of the reinforcement from the inner face.
- p , percentage of reinforcement. p' , ratio of the area of reinforcement to the area of concrete.
- c_w , stress in the concrete due to the weight and the wind.
- t_w , stress in the reinforcement due to the weight and the wind.
- P , total thrust on the section.
- F , total tension in the section.
- c_T , stress in the concrete due to fall of temperature across an uncracked section.
- c , maximum compressive stress in the concrete due to the weight, wind, and temperature.
- t , maximum stress in the reinforcement due to weight, wind, and temperature.
- R , mean radius of the chimney.
- S , shearing force. c_s , shearing stress in the concrete. t_s , shearing stress in the reinforcement.
- a , lever arm coefficient for a horizontal section.
- e , eccentricity.
- $K = \frac{c}{c_T}$. $C = (2n - K)$. $Q = \frac{t_w}{c_T}$. $U = \frac{c_w}{c_T}$.

The stresses in the concrete and reinforcement can be calculated for all cases, but the design will be governed by the worst cases, namely (i) compression of the concrete on the leeward side and (ii) tension in the reinforcement on the




Fig. 1.—Stresses due to Temperature Gradient.

windward side. It is assumed that the ratio of the thickness of the wall to the radius is very small and that all the tensile forces are resisted by the reinforcement.

An elemental vertical section is shown in Fig. 1. Due to the hot gases the inner surface becomes hot and there is a temperature gradient (T deg. Fahr.) between the inner and outer faces. As the expansion of the concrete at the inner face is restrained it is compressed and produces tensile forces in the reinforcement and in the concrete in the cooler parts such that the total forces and bending moments remain constant and the section remains plane and horizontal.

TEMPERATURE GRADIENT.—The bending moment in the section is $M = \frac{\alpha EIT}{d}$, where α is the coefficient of thermal expansion and E the modulus of elasticity. Since $c_T = \frac{My}{I}$, $c_T = \alpha ET \frac{y}{d}$. If the neutral axis passes through the centre of the section, $y = \frac{d}{2}$. Therefore $c_T = \frac{\alpha ET}{2}$. This is not the actual stress in the concrete due to the temperature gradient because, due to the presence of reinforcement, the neutral axis will be farther from the steel. It indicates, however, the rate of change of temperature stress in the section.

LEEWARD SIDE.—From Fig. 2, the thrust on the section per inch of length, neglecting the effect of temperature, is

$$c_w d [1 + p'(m - 1)] \quad (1)$$

The force in the reinforcement when subjected to high temperature is

$$\left(\frac{2nd}{d} c_T - c \right) mp'd \quad (2)$$

The reinforcement may be in tension or compression and, since the stress is small, the same modular ratio m is used in both cases. The error in the compressive stress in the concrete will not be very great.

The thrust on the section, including the effects of temperature, equals the thrust on the concrete less the tensile force in the reinforcement, that is,

$$P = \frac{1}{2} d \left(\frac{c}{c_T} \right)^2 c_T - \left(\frac{2nd}{d} c_T - c \right) mp'd \quad (3)$$




Fig. 2.—Stresses in Leeward Side.




Fig. 3.—Stresses in Windward Side.

For equilibrium, (1) - (3) = 0; that is

$$\frac{c^2}{4c_T} - (2nc_T - c)mp' - c_w(1 + p'(m - 1)) = 0 \quad (4)$$

or

$$\frac{c^2}{4c_T} + cmp' - [2nc_Tmp' + c_w(1 + p'(m - 1))] = 0.$$

Solving this equation,

$$c = 2c_T \left[-mp' + \sqrt{m^2p'^2 + 2nmp' + \frac{c_w}{c_T}(1 + p'(m - 1))} \right].$$

Assuming that $m = 15$ and $\frac{c_w}{c_T} = U$,

$$c = 2c_T [-15p' + \sqrt{225p'^2 + 30np' + u(1 + 14p')}] = Kc_T.$$

$$t = (2n - K)c_Tm = mCc_T = 15Cc_T.$$

Within limits, K is affected only negligibly by the amount of reinforcement. Graphs are given for $p = 0.5$, which gives fairly accurate results for up to 1 per cent. of reinforcement. The amount of reinforcement used is generally between 0.3 per cent. and 0.7 per cent.

WINDWARD SIDE.—The initial tensile force in the section is

$$t_w p' d \quad (1a)$$

The tensile force in the section, including the effects of temperature, equals the tension in the reinforcement less the thrust on the concrete. The tensile force in the reinforcement (Fig. 3) is

$$\left(\frac{2nd}{d} c_T - c' \right) mp' d \quad (2a)$$

The final tensile force is

$$\left(\frac{2nd}{d} c_T - c' \right) mp' d - \frac{1}{2} \frac{d(c')^2}{2(c_T)} c_T \quad (3a)$$

For equilibrium (1a) - (3a) = 0, that is

$$t_w p' d - \left(\frac{2nd}{d} c_T - c' \right) mp' d + \frac{d}{4} c_T \left(\frac{c'}{c_T} \right)^2 = 0,$$

or

$$\frac{c'^2}{4c_T} + c'mp' + t_w p' - 2nmp'c_T = 0 \quad (4a)$$

Solving (4a)

$$c' = 2c_T \left(-mp' + \sqrt{m^2p'^2 - \frac{t_w p'}{c_T} + 2nmp'} \right).$$

If $\frac{t_w}{c_T} = Q$ and $m = 15$,

$$c' = 2c_T [-15p' + \sqrt{225p'^2 + 30np' - Qp}] = K'c_T.$$

$c' = 0$ when $30np' = Qp'$ or $Q = 30n$, or $\frac{t_w}{c_T} = 30n$, that is when $t_w = 30nc_T$.

$$t = (2n - K')c_T m. \text{ If } c' = 0 \text{ then } K' = 0, t = 2mnc_T = 30nc_T.$$

Hence if, due to the dead load and the wind only, $t_w = 30nc_T$, there will be no change in the stress in the reinforcement regardless of the difference of temperature across the wall.

If the reinforcement is neglected in equation (4), then

$$\frac{d}{4} \frac{c^2}{c_T} = c_w d, \text{ or } c^2 = 4c_w c_T.$$

c can be a maximum when $c_w = c_T$. Therefore $c = 2c_w$ or $2c_T$ or $c_w + c_T$.

When the reinforcement is considered the maximum stress in the concrete can be little more than $c_w + c_T$, depending upon the value of n . Hence if c_w and c_T are nearly equal it is possible to estimate the stress in the concrete with reasonable accuracy. The use of these formulæ and graphs makes it unnecessary to calculate the position of the neutral axis due to temperature stresses only.

Use of Graphs I and II.

At a certain level a wall is $7\frac{1}{2}$ in. thick and the reinforcement comprises $\frac{1}{2}$ -in. bars at 5-in. centres with a cover of $1\frac{1}{2}$ in. to the outer face. At this level c_w on the leeward side is 350 lb. per square inch and t_w on the windward side is 3500 lb. per square inch. Also, when hot gases pass through the chimney the maximum difference in temperature in the concrete is 145 deg. Fahr. The coefficient of expansion of concrete is 6×10^{-6} per deg. Fahr., and the modulus of elasticity is 2×10^6 lb. per square inch. d is $7\frac{1}{2}$ in. Therefore

$$nd = 7\frac{1}{2} - (1\frac{1}{2} + \frac{1}{2}) = 5\frac{1}{2} \text{ in.}, \text{ and } n = \frac{5.75}{7.5} = 0.766.$$

The percentage of reinforcement is $\frac{0.471}{90} \times 100 = 0.523$.

$c_T = T\alpha E \frac{y}{d} = 135 \times 12 \times \frac{1}{2} = 810$ lb. per square inch. $\left(\frac{y}{d} = \frac{1}{2} \text{ when the section is uncracked.}\right)$

$$U = \frac{c_w}{c_T} = \frac{350}{810} = 0.432. \quad Q = \frac{t_w}{c_T} = \frac{3500}{810} = 4.32.$$


GRAPH I—(LEEWARD SIDE).—For $u = 0.432$ and $n = 0.766$, $K = 1.38$ and $C = 0.15$ (positive). $c = 1.38 \times 810 = 1118$ lb. per square inch.

$$t = 15 \times 0.15 \times 810 = 1820 \text{ lb. per square inch.}$$


GRAPH II—(WINDWARD SIDE).— $Q = 4.32$, $p = 0.523$, $K' = 0.486$, and $C = (2n - K') = 1.05$. Therefore $c' = 0.486 \times 810 = 394$ lb. per square inch and $t = 1.05 \times 15 \times 810 = 12,750$ lb. per square inch.

If the reinforcement is in compression on the windward side, t can be obtained from the formulæ for the leeward side and from Graph No. I.


GRAPH I.—STRESSES IN LEEWARD SIDE.



GRAPH II.—STRESSES IN WINDWARD SIDE.



GRAPH III.—SHEARING STRESSES.



Shear stress in concrete $C_s = \frac{S}{2\pi R d}$ where R = mean radius of chimney.
 Shear stress in Steel $t_s = \frac{S}{2\pi r d} \times 100$ S = Total shear at the section
 d = lever arm

In Combination with Horizontal Stresses.

Usually the shearing stresses in the concrete and the circumferential reinforcement due to wind pressure are small, so that when calculating c in the horizontal direction and the stress in the circumferential reinforcement the effect of the wind is often neglected and temperature only is taken into account. In this case it can be assumed that c_w and t_w are zero, so that u and Q are zero and c and t (the maximum stresses) can be obtained from the graphs. In some cases, however, it is better to combine t_s with c_r in order to obtain t . Since, due to the temperature, the concrete is cracked, the reinforcement should be able to resist the whole shearing force; c_s should be as small as possible.

$c_s = \frac{S}{2\pi R d}$, $t_s = \frac{S}{aR \times 2p'd}$ where p' refers to the circumferential reinforcement.




Fig. 4.—Cross Section.

The lever-arm coefficient a depends upon the position of the neutral axis, which depends upon $\frac{e}{R}$ where e is the eccentricity due to the wind (Fig. 4). In

Graph No. III $\cos \alpha$ connects the values of a with the values of $\frac{e}{R}$. In this case α is half the angle subtended by the neutral axis at the centre of the chimney. By substituting this value of a in the foregoing expression t_s is found, and this combined with c_r gives t for the worst conditions.

The following example illustrates the use of the graph. $R = 10$ ft.; $d = 6$ in.; the reinforcement comprises $\frac{1}{2}$ -in. bars at 6-in. centres. Therefore

$$p' = \frac{0.393}{6 \times 12} = \frac{0.393}{72} = 0.00546.$$

The load on the chimney is 500,000 lb. and a wind load of 100,000 lb. acts 40 ft. above the section. The bending moment due to wind is 4,000,000 lb.-ft. The equivalent area of the section

$$\begin{aligned} 2\pi R d (1 + 14p) &= 2\pi \times 10 \times 12 \times 6 (1 + 14 \times 0.00546) \\ &= 4860 \text{ sq. in. } e = \frac{4,000,000}{500,000} = 8 \text{ ft. } \frac{e}{R} = 0.8. \end{aligned}$$

$$c_s = \frac{100,000}{2 \times \pi \times 10 \times 12 \times 6} = \frac{100,000}{4,520} = 22.1 \text{ lb. per square inch.}$$

$$t_s = \frac{S}{2ap'Rd} = \frac{100,000}{2 \times 1.57 \times 0.00546 \times 120 \times 6} = 8100 \text{ lb. per square inch.}$$

(The value of a is found from *Graph No. III*.) This stress combined with that due to the temperature obtained from *Graph No. II* is the maximum stress in the circumferential reinforcement.

BIBLIOGRAPHY.—"Reinforced Concrete Chimneys", by Taylor and Turner. "Reinforced Concrete Masonry Structures", by Hool and Kinne.

The Design of Tee-beams.

By J. S. SAVONA.

REFERRING to *Fig. 1*, the symbols used are: b_f , breadth of flange; b_w , breadth of web; d_s , depth of slab; d , depth of beam; n , depth to neutral axis; ψ , the ratio $\frac{d_s}{n}$; $b_o = b_f - b_w$; $b_i = f(\psi)b_o$ and $f(\psi) = \psi(2 - \psi)$; $b_e = b_i + b_w$; A_t , area of tensile reinforcement; c , compressive stress.

The two lateral parts of the flange each of breadth $\frac{b_o}{2}$ and thickness d_s are reduced to equivalent breadth $\frac{b_i}{2}$ and depth n . Thus the tee-beam is reduced to a rectangular beam of breadth b_e equal to b_i added to b_w .

GRAPH I.





Fig. 1.

The total compression in the parts $\frac{b_o}{2}$ of the flange is

$$\frac{1}{2} \left[c + c \frac{(n - d_s)}{n} \right] b_o d_s = \frac{1}{2} c \frac{(2n - d_s)}{n} b_o d_s.$$

If b_i is the overall breadth of parts equivalent to $\frac{b_o}{2}$ and of depth n , the total compression is $\frac{1}{2} c b_i n$ (Fig. 1), but $\frac{1}{2} c b_i n = \frac{1}{2} c \frac{(2n - d_s)}{n} b_o d_s$. If $\psi = \frac{d_s}{n}$,

then $b_i = \psi(2 - \psi)b_o = f(\psi)b_o$ and the breadth of the equivalent rectangular beam is $b_e = b_i + b_w$. The relation between ψ and $f(\psi)$ is shown in Graph I.

EXAMPLE 1.—A tee-beam is subjected to a bending moment of 1,600,000 in.-lb.; b_f is 68 in.; b_w is 10 in.; d_s is 3.2 in. If the compressive stress in the concrete is 575 lb. per square inch and the tensile stress in the steel 20,000 lb. per square inch, and the modular ratio is 15, determine the depth of the beam and the area of reinforcement A_t .

Assume that $\psi = 0.475$. Then $b_o = b_f - b_w = 68 - 10 = 58$ in. Since $f(\psi) = 0.725$, $b_i = f(\psi)b_o = 0.725 \times 58 = 42$ in. Therefore $b_e = 42 + 10 = 52$ in. It will be found that d is 19.6 in. and n is 5.9 in., from which ψ is 0.53.

Assuming that $\psi = 0.65$, then b_e is 60.8 in., while the corresponding value of d is 18.9 in. and of n 5.73 in. This results in ψ equal to 0.575.

Assuming that ψ is 0.55, b_e is 56.3 in., d is 19.05 in., and n is 5.7 in. This results in an actual value of ψ of 0.557, which is very near the chosen value. The area of the reinforcement may now be calculated, and is 4.62 sq. in. It will be seen that the value of ψ fluctuates between the actual and assumed values until an assumption affords the required solution; two or three trials will suffice.

EXAMPLE 2.—A tee-beam has a breadth of flange of 72 in., d_s is 4 in., d is 24 in., and b_w is 15 in. If the beam has to resist a bending moment of 2,600,000 in.-lb. and the reinforcement consists of ten $\frac{7}{8}$ -in. bars ($A_t = 6.03$ sq. in.), determine the stresses in the concrete and steel. m is 15.

Assuming that $\psi = 0.46$, then $f(\psi) = 0.673$. $b_o = 72 - 15 = 57$ in. $b_i = 0.673 \times 57 = 38.3$ in. $b_e = 38.3 + 15 = 53.3$ in.

$$p = \frac{6.03}{53.3 \times 24} = 0.00471. \quad m p = 0.0708.$$

Hence $\alpha = 7.13^*$; $n_1 = 0.313$, $n = 7.52$ in., and $\psi = 0.532$.

Assuming that $\psi = 0.475$, then $f(\psi) = 0.725$, $b_i = 41.4$, $b_e = 56.4$ in.,

$$p = \frac{6.03}{56.4 \times 24} = 0.00446, \text{ and } m p = 0.0668.$$

Hence $\alpha = 6.47$, $n_1 = 0.35$, $n = 8.4$ in., and $\psi = 0.476$.

The last assumption is correct and the stresses are $c = 532$ lb. per square inch and $t = 14,880$ lb. per square inch.

* See this journal for May, 1954.

Reservoir with Walls of Novel Shape.

A RESERVOIR with a capacity of 25,000,000 gallons, divided into two unequal parts, is being built at Bushey Heath, Herts, for the Colne Valley Water Company. The western part is 523 ft. long by 238 ft. wide and has a capacity of 14,500,000 gallons. The eastern part is 313 ft. by 285 ft. and has a capacity of 10,500,000 gallons. The average depth of water is 21 ft. in both parts. There is a valve house at one end of the wall between the

The floor was cast in alternate bays each 30 ft. by 15 ft., and the construction joints are mid-way between the centres of the columns. Expansion joints are at intervals not exceeding 100 ft.

The reinforced concrete perimeter walls are of an unusual shape (Figs. 1 and 2). A "wall unit" comprises a base-slab 14 ft. wide incorporating a "floor beam" 4 ft. 6 in. deep, a lower section of wall 6 ft. high sloping outwards at 60 deg.



Fig. 1.—Perimeter Wall during Construction.

compartments. The inlet pipes which cross the floor of the reservoir are of reinforced concrete with flexible rubber joints and are anchored to precast concrete cradles. The pipes are 3 ft. diameter in the western part and 2 ft. 6 in. diameter in the eastern part.

The floor is 12 in. thick and reinforced in the top and bottom in both directions. The top reinforcement comprises twisted square bars in order to prevent surface cracks. The floor was laid on a blinding 3 in. thick covered with a single layer of bitumen emulsion to prevent adhesion.

and bearing against the excavated face, and an upper section of wall 20 ft. high sloping inwards at 60 deg. and incorporating a beam about mid-height. The floor and wall-beams are connected by sloping reinforced concrete members at 15-ft. centres. Expansion joints are at intervals not exceeding 90 ft. and there is a continuous expansion joint between the base of the wall and the floor-slab.

The wall is designed to resist the full head of water without embankments, the outward hydrostatic thrust being resisted by the lower sloping part of the wall and




Fig. 2.—Section Through Perimeter Wall.




Fig. 3.—Section Through Dividing Wall.




Fig. 4.—Arrangement of Precast Beams and Roof Units.

the floor-beam. The weight of earth on the top inwardly-sloping section of wall is slightly greater than the outward force due to the water pressure, and therefore the inner face of the wall will always be in compression. Other reasons for adopting this shape of wall are that on a restricted site additional storage capacity is obtained and less material is required for embankments. The extra storage capacity in the "bulge" of the wall is about 1,500,000 gallons, and the saving in material required for embankments amounted to about 10,000 cu. yd. The surplus excavated material was used for the construction of an earthen dam elsewhere in the Company's area.

The total length of the perimeter wall is more than 2000 ft., and therefore it was economical to provide special shuttering. The wall was constructed in sections 30 ft. long, each being built in four lifts. The first lift comprised the base-slab and the floor-beam, and included the building in of the raking struts which were precast with reinforcement protruding at each end. The second lift was the lower outwardly sloping part, followed by the inwardly-sloping part up to and including the wall-beam. The final stage was the top part above the wall-beam.

The dividing wall (*Fig. 3*) is vertical and at mid-height is strengthened by a beam tied to the floor-beams on either side by reinforced concrete members at 15-ft. centres. As in the case of the perimeter wall, the raking struts were precast and built into the base-slab.

The roof is formed almost entirely of precast members. The column bases were cast in situ on the floor slab, and on these

precast columns 12 in. square were erected. The main roof beams are prestressed precast members 30 ft. long and are supported on precast column caps. The heads of the columns were cast after the beams had been placed in position.

The roof comprises prestressed precast trough units 15 ft. long supported by the beams (*Fig. 4*). The gaps between the sloping sides of the roof units were filled with concrete which incorporated reinforcement over the top of the main beams to produce continuity.

All the prestressed roof members were designed so that their bottom surfaces are in compression under the dead load, which permits the lower part of the main beams to be submerged when the reservoir is full and reduces the total height required.

The roof is waterproofed with three layers of bituminous emulsion reinforced with two layers of glass fibre. Soil, 12 in. deep, is spread over the top of the roof and sown with grass. The floor has a slight fall towards the valve-house, and as the columns and perimeter wall are of equal height there is a slight fall on the roof to facilitate drainage.

The consulting engineers for the reservoir are Messrs. John Taylor & Sons, assisted by Messrs. Leslie Turner & Partners who gave advice on structural design. The contractors were Messrs. James Miller & Partners, Ltd. The contract sum was £315,610 which included all the work apart from bulk excavation and the concrete blinding layer, which had been previously laid by Messrs. W. & C. French, Ltd. All the precast reinforced and prestressed concrete units except the roof units were made by Shockcrete, Ltd.

Pulverised-fuel Ash in a Scottish Dam.

In the construction of Lednoch dam, near Comrie, Scotland, now in course of construction, about 100,000 cu. yd. of concrete will be used. The specified compressive strength is 2800 lb. per square inch at 28 days. The proportions are generally 1 part of cement to 10 parts of aggregate. Pulverised-fuel ash from the

North of Scotland Hydro-electric Board's power station at Barrhead is being used in replacement of 20 per cent. of the cement content. Similar concrete is being used in the construction of a dam at Glen Lyon. We are informed that the specified compressive strength has been obtained without difficulty.

Symposium on the Strength of Concrete Structures.

A SYMPOSIUM on the strength of concrete structures, arranged by the Cement and Concrete Association and the Joint Committee on Structural Concrete, was held in London in May. The following papers were presented.

"Some Results of the Theory of Probability in the Estimation of Design Loads", by M. R. Horne.

"The Determination of the Design Factor for Reinforced Concrete Structures", by Arne I. Johnson.

"Current Trends in the Specification of Structural Safety", by Professor Sir Alfred G. Pugsley, O.B.E.

"The Strength of Singly-reinforced Beams in Bending", by A. H. Mattock.

"The Strength of Concrete Members in Combined Bending and Torsion", by S. Armstrong.

"Strength of Prestressed Concrete Members", by Professor C. P. Siess.

"Moment Redistribution in Continuous Beams Reinforced with Plain and Deformed Bars", by K. Hajnal-Könyi and H. E. Lewis.

"The Failure of Concrete under Compound Stress", by A. J. Harris.

"Ultimate Load Design of Reinforced and Prestressed Concrete Frames", by Professor A. L. L. Baker.

"The Strength of Statically-indeterminate Prestressed Concrete Structures", by Y. Guyon.

"The Strength of Prestressed Concrete Continuous Beams and Simple Plane Frames", by P. B. Morice and H. E. Lewis.

"The Strength of Concrete Walls under Axial and Eccentric Loads", by A. E. Seddon.

"The Strength of Concrete Members under Dynamic Loading", by S. C. C. Bate.

"The Strength of Simply-supported Slab Bridges subjected to Concentrated Loads", by P. B. Morice and G. C. Reynolds.

"Ultimate Strength of Reinforced Concrete in American Design Practice", by Eivind Hognestad.

"The Design of Reinforced Concrete Members", by A. Aas-Jakobsen.

"Load-factor Design in Building Regulations: Future British Practice", by D. D. Matthews.

The Reinforced Concrete Association.

THE annual general meeting of the Reinforced Concrete Association was held in London on June 6. The officers for the ensuing year were elected as follows:

President: Mr. F. S. Snow, O.B.E. (F. S. Snow & Partners).

Vice-President: Mr. E. J. Cook (Richard Costain, Ltd.).

Members: Messrs. E. Bellringer (Stothert & Pitt, Ltd.), E. L. V. Dakin, M.C. (Wilson Lovatt & Sons, Ltd.), P. H. T. Gooding (Cement & Concrete Association), D. P. Harris (Taylor Woodrow Construction, Ltd.), H. S. Killick, M.C. (Twistee Reinforcement, Ltd.), W. K. Laing (John Laing & Son, Ltd.), A. Raymond Mais, O.B.E. (Trollope & Colls, Ltd.), L. J. Murdock (George Wimpey & Co., Ltd.), A. R. Neelands, M.C. (Cementation Co., Ltd.), H. F. Rosevear (Sir Robert McAlpine & Sons, Ltd.), E. S. Shellard (Associated Portland Cement Manufac-

turers, Ltd.), C. W. J. Spicer (Considère Constructions, Ltd.), G. W. Stokes (Matthews & Mumby, Ltd.), F. W. Sully [Holloway Bros. (London), Ltd.].

Associates: Messrs. M. G. C. Ayre, C. V. Blumfield, F. C. Eales, A. W. Hill, E. Shepley, J. Singleton-Green, and D. A. Stewart.

Branch Delegates: Messrs. E. J. Martin (Holst & Co., Ltd.), North Western Branch; A. P. Mason (British Reinforced Concrete Engineering Co., Ltd.), Midland Counties Branch; W. A. Fairhurst (F. A. Macdonald & Partners), Scottish branch.

The retiring President (Mr. D. H. New, of Holland & Hannen and Cubitts, Ltd.) presided at the annual luncheon held on the same day, and presented the Association's medal for the past year to Mr. J. A. Derrington for his paper on "Precasting Concrete Structures".

General Formulæ for Maximum Bending Moments.

IMAGINARY DIVERSITY OF LOAD.

By L. S. MÜLLER.

An assumption of an imaginary diversity of load is a useful method of deriving general formulæ for the maximum bending moments of certain continuous structures. If one set of loads is required to cause maximum bending moments at the supports or corners, the application of another, necessarily different, set of loads is required to obtain the maximum moments within the span. By the use of this principle general formulæ may easily be derived in a form in which equating some of the loads (initially assumed as different) to each other, some of them to zero or to the total load, and others to the dead load, will provide formulæ for the different maxima bending moments. This makes it unnecessary to deal separately with dead and live loads.

The principle is explained by two examples chosen to show the application of the method to common problems.

EXAMPLE I.—THREE RECTANGULAR TANKS OR SILOS (Fig. 1).—In this case the slope-deflection method is used and it is assumed that the pressures are w_1 , w_2 , and w_3 . In order to define the rotations consistently assume that w_1 is greater than w_3 and w_3 is less than w_2 . For simplicity, assume that the stiffness of the members is constant, and therefore, the stiffnesses and Young's modulus E may be omitted from the equations.

$$\text{For point A: } 4 \times 2\theta_A + 2\theta_B + 2\theta_H + \frac{w_1(l_2^2 - l_1^2)}{12} = 0$$

$$\text{" " B: } 4 \times 3\theta_B + 2\theta_A + 2\theta_C + 2\theta_G - \frac{(w_1 - w_2)(l_2^2 - l_1^2)}{12} = 0$$

$$\text{" " C: } 4 \times 3\theta_C + 2\theta_B + 2\theta_D + 2\theta_F + \frac{(w_3 - w_2)(l_2^2 - l_1^2)}{12} = 0$$

$$\text{" " D: } 4 \times 2\theta_D + 2\theta_C + 2\theta_E + \frac{w_3(l_1^2 - l_2^2)}{12} = 0$$

Since $\theta_H = -\theta_A$, $\theta_G = -\theta_B$, $\theta_F = -\theta_C$, and $\theta_E = -\theta_D$, the solutions of the four simultaneous equations are

$$\theta_A = -\frac{8lw_1 - 17w_2 + 4w_3}{374} \cdot \frac{(l_2^2 - l_1^2)}{12}, \quad \theta_B = \frac{56w_1 - 5lw_2 + 12w_3}{374} \cdot \frac{(l_2^2 - l_1^2)}{12}.$$




Fig. 1.—Three Rectangular Tanks.

$$\theta_C = -\frac{12w_1 - 51w_2 + 56w_3}{374} \cdot \frac{(l_2^2 - l_1^2)}{12}, \quad \theta_D = \frac{4w_1 - 17w_2 + 81w_3}{374} \cdot \frac{(l_2^2 - l_1^2)}{12}.$$

From these

$$M_{AB} = 2(2\theta_A + \theta_B) - \frac{w_1 l_1^2}{12} = \frac{l_2^2 - l_1^2}{187 \times 12} (-106w_1 - 17w_2 + 4w_3) - \frac{w_1 l_1^2}{12}.$$

By substituting

$$\frac{l_2}{l_1} = m, \quad M_{AB} = \frac{1}{187} \cdot \frac{l_1^2}{12} [- (81 + 106m^2)w_1 + 17(1 - m^2)w_2 - 4(1 - m^2)w_3]$$

$$\text{Similarly } M_{BA} = \frac{1}{187} \cdot \frac{l_1^2}{12} [(156 + 31m^2)w_1 + 85(1 - m^2)w_2 - 20(1 - m^2)w_3]$$

$$M_{BC} = \frac{1}{187} \cdot \frac{l_1^2}{12} [-100(1 - m^2)w_1 - (136 + 51m^2)w_2 + 32(1 - m^2)w_3]$$

$$M_{BG} = \frac{1}{187} \cdot \frac{l_1^2}{12} [- (56 + 131m^2)w_1 + (51 + 136m^2)w_2 - 12(1 - m^2)w_3]$$

For the maximum value of M_{AB} and also for the maximum moment on the span AH, $w_1 = w_3 = w$, and $w_2 = 0$. $M_{AB}(\max.) = M_{AH}(\max.) = -M_{HA}(\max.)$

$$= -\frac{1}{187} \cdot \frac{w l_1^2}{12} (85 + 102m^2) = -w l_1^2 \left(\frac{1}{22} + \frac{1}{26.4m^2} \right)$$

Therefore, for member AH

$$+ M_{(\max.)} = \left[\frac{1}{8} - \left(\frac{1}{22} + \frac{1}{26.4m^2} \right) \right] w l_1^2 = \frac{2.1m^2 - 1}{26.4m^2} \cdot w l_1^2.$$

For maximum moment within the span AB the conditions are as before, so that

$$M_{AB} = - \left(\frac{m^2}{22} + \frac{1}{26.4} \right) w l_1^2$$

and

$$M_{BA} = \frac{1}{187} \cdot \frac{w l_1^2}{12} (136 + 51m^2) = \left(\frac{1}{16.5} + \frac{m^2}{44} \right) w l_1^2,$$

from which

$$+ M_{(\max.)} = \left(\frac{1}{13.2} - \frac{m^2}{28.8} + \frac{m^4}{3880} \right) w l_1^2$$

For $M_{BA}(\max.)$, $w_1 = w_2 = w$ and $w_3 = 0$.

$$\text{Therefore } M_{BA}(\max.) = \frac{1}{187} \cdot \frac{w l_1^2}{12} (241 - 54m^2) = \left(\frac{1}{9.3} - \frac{m^2}{41.5} \right) w l_1^2$$

and with the same conditions,

$$M_{BC}(\max.) = -\frac{1}{187} \cdot \frac{w l_1^2}{12} (236 - 49m^2) = - \left(\frac{1}{9.5} - \frac{m^2}{45.8} \right) w l_1^2$$

For maximum moment on the span BC, $w_1 = w_3 = 0$, and $w_2 = w$.

$$\text{Therefore } M_{BC} = M_{CB} = \mp \frac{1}{187} \cdot \frac{w l_1^2}{12} (136 + 51m^2) = \mp \left(\frac{1}{16.5} + \frac{m^2}{44} \right) w l_1^2,$$

$$\text{so that } + M(\max.) = \left(-\frac{1}{8} - \frac{1}{16.5} - \frac{m^2}{44} \right) w l_1^2 = \left(\frac{1}{15.5} - \frac{m^2}{44} \right) w l_1^2$$

For maximum moment in the span BG:

(a) If $m \leq 1$, $w_1 = w_3 = 0$ and $w_2 = w$.

$$\begin{aligned} \text{Therefore } -M_{GB} = M_{BG} &= \frac{1}{187} \cdot \frac{wl_1^2}{12} (51 + 136m^2) \\ &= \frac{1}{187} \cdot \frac{wl_1^2}{12} \left(\frac{51}{m^2} + 136 \right) = \frac{2.67m^2 + 1}{44m^2} \cdot wl_2^2 \end{aligned}$$

$$\text{and } +M(\text{max.}) = \left(\frac{1}{8} - \frac{2.67m^2 + 1}{44m^2} \right) wl_2^2 = \frac{2.83m^2 - 1}{44m^2} \cdot wl_2^2$$

(b) If $m \geq 1$, $w_1 = w_3 = w$ and $w_2 = 0$.

$$\text{Therefore } M_{BG} = -M_{GB} = -\frac{1}{187} \cdot \frac{wl_1^2}{12} (68 + 119m^2) = -\frac{1.75m^2 + 1}{33m^2} \cdot wl_2^2$$

$$\text{and } +M(\text{max.}) = \left(\frac{1}{8} - \frac{1.75m^2 + 1}{33m^2} \right) wl_2^2 = \frac{2.38m^2 - 1}{33m^2} \cdot wl_2^2$$

The conditions for maximum bending moments at the corners for cases (a) and (b) respectively are the same as for the maximum moments in the span in cases (b) and (a) respectively.

EXAMPLE 2.—Derive formulæ for the maximum bending moments at the supports of continuous beams with three unequal spans supported by unyielding supports, each span having a different moment of inertia. The load is $w = g + p$ where g is the dead load and p is the live load. Assume a different load, w_1 , w_2 , and w_3 , for each span (Fig. 2). From Clapeyron's equations,

$$2M_1 \left(\frac{l_1}{I_1} + \frac{l_2}{I_2} \right) + M_2 \frac{l_2}{I_2} = -\frac{w_1 l_1^3}{4I_1} - \frac{w_2 l_2^3}{4I_2};$$

$$M_1 \frac{l_2}{I_2} + 2M_2 \left(\frac{l_2}{I_2} + \frac{l_3}{I_3} \right) = -\frac{w_2 l_2^3}{4I_2} - \frac{w_3 l_3^3}{4I_3}$$

Writing $\frac{l_1}{I_1} = K_1$, $\frac{l_2}{I_2} = K_2$, and $\frac{l_3}{I_3} = K_3$ the solution is

$$M_1 = -\frac{K_1}{K_1(4K_2 + 3K_3) + 4K_2(K_2 + K_3)} \left[\frac{K_2(K_2 + K_3)}{2K_1} \cdot w_1 l_1^3 + \frac{2K_2 + K_3}{4} \cdot w_2 l_2^3 - \frac{K_2 w_3 l_3^3}{4} \right]$$

$$M_2 = -\frac{K_2}{K_1(4K_2 + 3K_3) + 4K_2(K_2 + K_3)} \left[-\frac{K_2}{4} \cdot w_1 l_1^3 + \frac{K_1 + 2K_2}{4} \cdot w_2 l_2^3 + \frac{K_2(K_1 + K_3)}{2K_3} \cdot w_3 l_3^3 \right]$$




Fig. 2.—Continuous Beam.

With the usual assumption that $I_1 = I_2 = I_3 = I$, that is $K_1 = \frac{I}{l_1}$, $K_2 = \frac{I}{l_2}$, and $K_3 = \frac{I}{l_3}$, and relating all bending moments to the internal span l_2 by writing $\frac{l_1}{l_2} = m$ and $\frac{l_3}{l_2} = n$,

$$M_1 = -\frac{n}{3 + 4(m + n + mn)} \left[\frac{m^3}{2} \cdot \frac{n + 1}{n} \cdot w_1 + \frac{2n + 1}{4n} \cdot w_2 - \frac{n^2}{4} \cdot w_3 \right] \cdot l_2^2$$

$$M_2 = -\frac{m}{3 + 4(m + n + mn)} \left[-\frac{m^2}{4} \cdot w_1 + \frac{2m + 1}{4m} \cdot w_2 + \frac{n^3}{2} \cdot \frac{m + 1}{m} \cdot w_3 \right] \cdot l_2^2$$

The decisive load for the maximum bending moments within the first and third spans is $w_1 = w_3 = w$ and $w_2 = g$, hence

$$M_1' = -\frac{n}{3 + 4(m + n + mn)} \left[\left(\frac{m^3}{2} \cdot \frac{n + 1}{n} - \frac{n^2}{4} \right) w + \frac{2n + 1}{4n} \cdot g \right] \cdot l_2^2$$

$$M_2' = -\frac{m}{3 + 4(m + n + mn)} \left[\left(-\frac{m^2}{4} + \frac{n^3}{2} \cdot \frac{m + 1}{m} \right) w + \frac{2m + 1}{4m} \cdot g \right] \cdot l_2^2$$

The decisive load for the maximum bending moment within the second span is $w_1 = w_3 = g$ and $w_2 = w$. Hence

$$M_1'' = -\frac{n}{3 + 4(m + n + mn)} \left[\left(\frac{m^3}{2} \cdot \frac{n + 1}{n} - \frac{n^2}{4} \right) g + \frac{2n + 1}{4n} \cdot w \right] \cdot l_2^2$$

$$M_2'' = -\frac{m}{3 + 4(m + n + mn)} \left[\left(-\frac{m^2}{4} + \frac{n^3}{2} \cdot \frac{m + 1}{m} \right) g + \frac{2m + 1}{4m} \cdot w \right] \cdot l_2^2$$

The maximum bending moments at the supports for $w_1 = w_2 = w$ and $w_3 = g$ are

$$M_1(\max.) = -\frac{n}{3 + 4(m + n + mn)} \left[\left(\frac{m^3}{2} \cdot \frac{n + 1}{n} + \frac{2n + 1}{4n} \right) w - \frac{n^2}{4} g \right] \cdot l_2^2$$

For $w_1 = g$ and $w_2 = w_3 = w$,

$$M_2(\max.) = -\frac{m}{3 + 4(m + n + mn)} \left[-\frac{m^2}{4} g + \left(\frac{2m + 1}{4m} + \frac{n^3}{2} \cdot \frac{m + 1}{m} \right) w \right] \cdot l_2^2$$

Evidently, if $m = n = 1$, that is the three spans are equal,

$$M_1' = M_2' = M_1'' = M_2'' = -\left(g + \frac{p}{2} \right) \frac{l^2}{10}$$

and
$$M_1(\max.) = M_2(\max.) = -\left(\frac{g}{10} + \frac{7p}{60} \right) l^2.$$



Tricosal is the proved Waterproofing and
Hardening medium

Rigid and steel-hard results obtained by

Including Tricosal with new cement work

Concrete Waterproofed permanently

Overcomes dusting

Secures high oil and acid-resistance

And ensures a

Longer life to all cement work

let the **FOUNDATIONS**
of your plans be **TRICOSAL**

A. A. BYRD AND CO., LIMITED (Dept. S)
210, Terminal House, Grosvenor Gardens, London, S.W.1

*Phone : SLOane 5236.

*Grams : Byrdicom, Wesphone, London.

COSTAIN CONCRETE CO. LTD.**DUNCAN HOUSE, DOLPHIN SQUARE, LONDON, S.W.1.****TELEPHONE:— VICTORIA 3172/4**

**for
High Quality
Precast and Prestressed
Concrete**

LONDON UNIT FACTORY

*Stahlton Lane, Southend Arterial Road,
Childerditch, Nr. Brentwood, Essex
Tel.: Herongate 317*

SCOTLAND**COLTNESS FACTORY**

*Newmains, Lanarkshire
Tel.: Wishaw 880*

LANCS. YORKS. & MIDLANDS

*R. Costain & Sons (Liverpool) Ltd.,
Barlow Lane, Fazakerley, Liverpool 9
Tel.: Aintree 4141/5*

WALES

*Cowbridge Road,
BRIDGEND, Glamorgan
Tel.: Bridgend 961*

Stahlton PRESTRESSED FLOORS

Experimental Road in Nottinghamshire.

A NEW section of the experimental concrete road known as the Oxtun by-pass, which connects the Leicester to Newark road (A46) and the Nottingham to Bawtry road (A614), has been completed. Part of the by-pass was built before the war. In a further section, begun in 1946, experiments were made with reinforced and unreinforced slabs of various thicknesses. In 1955 work was started on the southern half of the by-pass, and methods were used that were considered to be suitable for much larger works and also for improving the riding qualities of concrete roads and gaining experience in applying to roads the methods used for the rapid construction of airfield runways. A high standard of riding quality was set for this road with an irregularity index of not more than 40 in. per mile. The carriage-way is 8 in. thick, 24 ft. wide, and 1300 yd. long. The concrete was made with ordinary Portland cement mixed in the proportions of 1 : 6.25 and had a water-cement ratio varying from 0.55 to 0.58. The coarse aggregate was in two sizes and was mixed with sand in the proportions of 2 parts sand, 1.6 parts $\frac{3}{4}$ in. aggregate and 3 parts $\frac{1}{4}$ in. aggregate. These proportions were varied slightly during the course of the work. Test cores had an average strength equivalent to cubes with a 28-day strength of 7000 lb. per square inch.

The arrangement of the plant is shown in Fig. 2. The cement and aggregate were




Fig. 1.—Supplying Concrete to Hopper of Machine.

weighed and batched at a central plant and taken in a dry state to the mixer behind the road-making machine, where they were mixed at a rate of 60 cu. yd. per hour. Water was delivered in "tanker" road vehicles. The concrete was spread by a new type of machine designed by the contractors, Messrs. John Laing & Son, Ltd. The concrete was




Fig. 2.—The Road-making Machine.




Fig. 3.—The Tamping and Finishing Beams.

emptied from the mixer into a bottom-opening bucket, which was moved along a beam and emptied into a hopper on the machine spanning the full width of the slab (Fig. 1). Below the hopper were two screws, one left-handed and the other right-handed, which distributed the concrete across the road. The concrete was levelled as the machine moved forward.

The spreader was followed by a vibrating compacting beam and an oscillating smoothing beam (Fig. 3). This was followed by a profilometer, which recorded any deviation from the required surface. Such deviations were corrected by returning the beams to repeat the operation. The spreader, finishing beams, and profilometer were mounted on rails fixed to the steel forms along the edge of the slab. These forms were 10 ft. long and 8 in. deep, and were laid on a previously-prepared concrete foundation.

A mesh of reinforcement weighing about 10 lb. per square yard was placed about $2\frac{1}{2}$ in. below the surface of the slab. Instead of supporting the reinforcement on stirrups as is customary, it was supported on a skid which was moved forward by the spreader. After the machine had moved on, the surface of the concrete was brushed to increase its resistance to skidding and to diminish glare from the sun or headlights, and was then sprayed with a curing liquid.

Expansion joints are at intervals of 90 ft. to 120 ft. The joint was made by a wooden board $\frac{3}{4}$ in. thick and 6 $\frac{1}{2}$ in. deep placed across the width of the road



Fig. 4.—An Expansion Joint.



Fig. 5.—Cutting a Joint.

RITECLURE

membrane curing

**USED FOR CURING
OVER 23 MILLION
YARDS OF CONCRETE
IN THE BRITISH ISLES**

Riteclure produces an impervious film which provides controlled moisture retention throughout the curing period of 28 days.

Riteclure should be sprayed on the concrete immediately after finishing. Spraying is a one man operation.

Riteclure is complete in itself requiring no covering down or wetting. One coat only is required.

Riteclure (Pigmented) eliminates the need for covering with hoods as called for on Air Ministry contracts, showing considerable saving on curing costs.

Write for our Technical Leaflets and Specifications

STUART B. DICKENS LIMITED

36 Victoria Street, London, S.W.1. Tel: Abbey 4930


Works: Old Milton Street, Leicester. Tel: Leicester 20390




SMITH'S

FIREPROOF FLOORS


- The most adaptable System of Suspended Hollow
- Concrete Floor and Roof Construction for large •
 - and small spans.



Showing Two-Way Reinforcement and Hollow Concrete Blocks laid on Trianco Telescopic Centers.



Smith's Two-Way Reinforced Floor for distribution of point loads with efficiency and economy.



Illustrating the continuous Soffit with natural Key to which plaster readily adheres without hacking or other preparation to form finished ceiling.

**2 WAY REINFORCED
SUSPENDED
CONCRETE FLOORS**

Midland Associated Company &
Licensees
**PARKFIELD CONCRETE PRODUCTS
COMPANY LIMITED**
St. Peter's Road
**NETHERTON, Nr. DUDLEY
WORCS.**
'PHONE: DUDLEY 4315

SMITH'S FIREPROOF FLOORS LTD
IMBER COURT • EAST MOLESEY • SURREY

EMBerbrook 3300 (4lines)



Manufacturers of

PRESTRESSED MEMBERS

PRECAST UNITS

& STRUCTURES

An Advisory Service for scheme proposals and cost is readily available



CONCRETE DEVELOPMENT COMPANY LIMITED

THORNEY LANE • IVER • BUCKS • TEL: IVER 1131

923A 61A

(Fig. 4). Dowel bars 2 ft. long, with a cardboard cap at one end to allow for expansion, were placed in position in the board. A triangular fillet was placed on the top of the board with its apex $\frac{3}{8}$ in. below the surface of the concrete, so as to ensure that shrinkage cracks would be confined to this line. The machine moved across the joint, placing concrete without interruption.

When the concrete had hardened a diamond saw was used to cut through the concrete above the wooden joint-filler (Fig. 5) and the fillet was removed. The groove so formed was then cleaned, primed and filled with a sealing material. A dummy joint was cut longitudinally along the centre of the road to prevent any irregular cracking across the centre of the slab.

Britain's First Motor Road Started.

WORK on a new road exclusively for the use of motor vehicles, and the first of its kind in this country, started in June. The new road, known as the Preston by-pass, will be more than eight miles long and will be the first part of the proposed north to south motorway from Birmingham to north of Shap. The section now started will extend from near the junction of the A6 and A49 roads at Bamber Bridge to the Preston-Lancaster road south of Broughton.

The new road will have dual carriage-

ways each 24 ft. wide with space to widen them to 36 ft. There will be no kerbs, but the sides of the road will be marked by a coloured strip beyond which will be a parking strip 8 ft. wide. Side roads and footpaths will pass under or over the road. There will be no footpaths. The work includes two welded-steel bridges. It is estimated that the work will cost £3,000,000 and will require about two years to complete. The scheme was prepared by the Surveyor and Bridge-master of the Lancashire County Council.

July, 1956.

Centering for Ribbed Floors.

THE following notes describe the hollow concrete floors at a hospital recently completed at Limerick, Eire, at a cost of about £1,000,000. The floor and roof slabs generally are of "hollow steel mould" construction, having spans up to 26 ft. and overall thicknesses of floors varying from 12 in. to 15 in. These floors have a total area about 180,000 sq. ft., and are designed for imposed loads of 30 lb. to 100 lb. per square foot in addition to finishes and partitions.

The floors (Fig. 1) consist of thin reinforced concrete ribs at about 2 ft. centres with a 2-in. reinforced concrete slab on

The shoes shown in the illustration were 5 in. wide, but widths of 3 in. and 3½ in. are also supplied. As the moulds are of standard width, the spacing of the ribs varies with the dimension of the shoe between 1 ft. 11½ in. and 2 ft. 2 in. Where the ribs meet beams or walls, steel end-pieces are used to form side shutters between the ribs. Alternatively these stop-ends may be made of timber on the site.

In the main blocks of this hospital the wards have balconies on to which the beds can be moved; these are cantilevered parts of the floor slabs, and some of the




Fig. 1.

top to form tee-beams and to provide the floor surface. The trough-shaped steel moulds which form the centering are in standard lengths of 2 ft. and 3 ft., and these sizes, with cover moulds 1 ft. 2 in. long, are used for any required span. The moulds are fixed by wedging them into channel-shaped shoes previously fixed on the staging. Fig. 2 shows a method of setting out the shoes on timber bearers, but special couplers are available if the whole of the staging is of tubular steel. The moulds are in depths of 9 in. and 15 in., and the ribs may be in depths of 4 in. to 15 in. by the use of timber blocking pieces. Spans may be up to 31 ft. in prestressed concrete and up to 45 ft. in reinforced concrete. Fig. 3 shows the centering in position.


moulds were omitted to permit the floors to be solid where they are subjected to compression due to the cantilever. The partitions generally are carried on the ribbed floors, but where heavy partitions and local loads occur the moulds were spaced farther apart in order to form wider ribs. Construction joints were usually formed in the 2-in. topping, half way between ribs, by the use of strips of timber which also kept the mesh reinforcement in position and acted as screeds. Construction joints were formed at right-angles to the direction of the ribs and at the centre of the span.

The total weight of the centering in position, but excluding propping, is 75 lb. per square yard in the case of 15-in. moulds and 60 lb. per square yard in the

Specialists in



Reinforced



Concrete



STAVERTON

BUILDERS LIMITED



Building and Civil Engineering Contractors
TOTNES DEVON

OFFICES AT: LONDON • CARDIFF • BRISTOL • PLYMOUTH

STERNSON

CONCRETE WATERPROOFERS

CONCRETE WATERPROOFING
MATERIALS
ACCELERATORS
FLOOR HARDENERS
BONDING MATERIALS, ETC.

Sternson No. 300	Waterproofing Admixture for Concrete and Mortar.
Sternson No. 310	Concrete Accelerator, Hardener and Dustproof.
Sternson No. 340	Concrete Accelerator, Hardener and Dustproof.
Sternson No. 355	To Rapid-Set Cement for Waterproofing Operations.
Sternson No. 600	Metallic Jointing Material for Concrete or Brick.
Sternson No. 610	Metallic Bonding Between Old and New Concrete.
Sternson No. 620	Metallic Hardener for Heavy Duty Concrete Floors.

Other Materials include:

WETTING AGENTS
MASTIC IRON
PLAIN AND COLOURED
WAX POLISHES, ETC.

Write for our Technical Leaflets and Specifications

STUART B. DICKENS LIMITED

36 Victoria Street, London, S.W.1. Telephone: Abbey 4930

Works: Old Milton Street, Leicester. Telephone: Leicester 20380




Fig. 2.

case of 9-in. moulds. The weight of this type of floor suitable for an imposed load of 80 lb. per square foot over a span of, say, 26 ft., is about 57 lb. per square foot.

Use was made of the spaces between the ribs for the installation of electrical services, hot and cold water supplies, waste pipes, and low-pressure hot-water heating. As far as possible the pipes and conduits are in the direction of the spans of the ribs, but where necessary pipe-sleeves were cast into the ribs to permit the passage of services at right angles to the span. Strips of cedarwood of splayed section were cast into the soffit of each rib (Fig. 1); to these, battens were fixed at 14-in. centres to carry plaster slabs finished with a skim coat of plaster. An alternative method of fixing the ceiling to the ribs is a permanent soffit lining piece 1 in. thick made of creosoted softwood and secured to the concrete by galvanised-wire ties. This generally provides a truer soffit line and a neater finish, but has the disadvantage that the maximum depth of rib possible is reduced to 8 in. for 9-in. moulds and to 14 in. for




Fig. 3.

15-in. moulds. Ceilings with metal hangers can be suspended from the ribs during casting, or the floor can be finished without a ceiling to expose the soffit of the ribs; this treatment was used in the boiler-house where the roof is 20 ft. above the floor. Where insulation is important, a roof of this type might be finished with sprayed asbestos instead of roughcast.

The architect for the Limerick Regional Hospital Board is Mr. Patrick J. Sheahan, K.S.S., F.R.I.A.I., M.I.C.E.I., who designed the building in consultation with Messrs. Stanley Hall, Easton and Robertson. The structural designs were prepared by the British Reinforced Concrete Engineering Co., Ltd., who are the proprietors of the "hollow steel mould" construction described. The general contractors were Messrs. Murphy Brothers (Cork), Ltd.

The Treatment of Concrete with Silicones.

It is reported in "Engineering News-Record" for November 24, 1955, that many concrete bridges on the New York State Thruway have been treated with a silicone solution to reduce the effect of freezing and thawing. The Authority states that silicone, by reversing the capillary attraction of concrete, reduces moisture absorption more effectively than any other surface treatment.

The specifications of New York State require air-entrained concrete to be used in bridge decks, but about 500 earlier bridges were built with a mixture of natural and Portland cements. Of these, 160 that are maintained by the Authority are being treated with silicone. Ultimately, this treatment will be given to decks built with air-entrained concrete.

The silicone treatment will replace the oil-spray treatment; where the silicone treatment has been applied to bridges that had been treated with oil the water repellency of the surface was greatly increased. It is stated that silicone is

hydrophobic, rapidly dries out without any tendency to attract air-borne dust and dirt, and its resistance to oxidation indicates that it retains its ability to repel water for longer than the best organic oils.

A spraying equipment for treating the bridges consists of a tank of 230 gallons capacity mounted on a truck together with a rotary pump driven by a 5-h.p. petrol engine. This pump supplies a 14-ft. spray bar made up of a 6-ft. section and two independently controlled 4-ft. sections to provide flexibility. There are also two hand spray-bars for work that cannot be reached by the main spray-bars. The truck that carries the tank and spray has an operating speed of about three miles an hour. One gallon of 2 per cent. silicone solution covers about 100 sq. ft. and the cost is about 32s. per gallon of 20 per cent. solution. The bridge decks are swept with rotary brushes in advance of the treatment, to ensure that dust does not absorb much of the solution.

Ensure safety : use
**DORMAN LONG
STEEL
TRENCH SHEETING**

(Regd. design
No. 850839)

**Prompt
Delivery**

For the temporary lining of trenches and foundations. *Prices and full particulars on application to:—*

**DORMAN LONG (Steel) LTD., SHEET DEPT.
AYRTON WORKS, MIDDLESBROUGH**

London Office: Terminal House, 52 Grosvenor Gardens, S.W.1.

DORMAN LONG

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 4d. a word : minimum, 7s. 6d. Situations Vacant, 5d. a word : minimum, 10s. Other miscellaneous advertisements, 5d. a word : 10s. minimum. Displayed advertisements, 35s. per column inch. Box number 1s. extra.

Advertisements for the August number must reach this office by July 14th

SITUATIONS VACANT.

SITUATIONS VACANT. Senior reinforced concrete designers wanted by leading reinforced concrete engineers and contractors. Must be fully conversant with Code of Practice, L.C.C. Bye-Laws, and able to design light-framed structures from estimating stage to final details. Five-days' week. Pension scheme. Progressive position. Starting salary from £900 upwards according to ability. This year's holiday arrangements honoured. Juniors also required, similar conditions. Write Box 4172, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Assistant structural engineers required with experience of reinforced concrete design. Experience of precast techniques advantageous. Salary according to experience and qualifications. Apply in writing to TECHNICAL MANAGER, THE SCOTTISH CONSTRUCTION CO., LTD., Sighthill Industrial Estate, Edinburgh.

SITUATION VACANT. Reinforced concrete design engineer required by specialist reinforcement designer/suppliers. A.M.I.Struct.E. essential, preferably with constructional experience. Permanent superannuated position with scope for advancement. Write or telephone ROW RIVER CO., LTD., St. Richard's House, Eversholt Street, London, N.W.1. Euston 7814.

SITUATION VACANT. Civil engineering draughtsman required for work in London office of large civil engineering contractors. Work of varied nature, with scope for initiative and advancement. Commencing salary £600-£800 depending on experience. Five-days' week and luncheon vouchers. Pension scheme operates. Box 4228, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. TAYLOR WOODROW CONSTRUCTION, LTD., require senior and assistant technical staff in the following categories:

Structural Design Engineers with reinforced concrete experience, for Head Office.

Site Civil Engineers. Interesting and progressive positions for the right men. Well-paid and pensionable posts. Write, giving full details, which will be treated confidentially, to M.D. Engineer, Ruislip Road, Sou'ham, Middlesex.

SITUATIONS VACANT. Reinforced concrete designers and detailers (senior and junior) required by consulting engineers for varied and interesting building frames and industrial structures. Good prospects. Five-days' week. Lunch vouchers. Apply, with details of training and/or experience, etc., to JOHN FARQUHARSON & PARTNERS, 34 Queen Anne Street, London, W.1. Langham 6081.

SITUATIONS VACANT. Site engineers required for reinforced concrete framed structures in London area and provinces. Applicants must be over 35 years of age, and thoroughly experienced in all classes of reinforced concrete work. Good salaries offered to the right men. Apply in writing to J. H. COOMBS & PARTNERS, Consulting Engineers, Thames Corner, Sunbury-on-Thames, Middlesex.

LONDON COUNTY COUNCIL

ARCHITECT'S DEPARTMENT

Vacancies for Engineering Assistants (up to £918) and Engineer Grade III (up to £987) in the Structural Engineering Division. Work includes steelwork and reinforced concrete design and detailing for Council's buildings. Particulars and application forms from ARCHITECT (AR/EK/SE/3), The County Hall, London, S.E.1. (1278.)

SITUATION VACANT. Consulting structural and civil engineers require an engineering assistant with at least 5 years' office experience since Graduateship and National Service, to supervise the design and detailing of reinforced concrete structural frameworks and foundations. Salary £750-£900 according to age, qualifications and experience. Superannuation scheme, and luncheon vouchers. Apply ANDREWS, KERT & STONE, 60-66 Wardour Street, London, W.1.

SITUATION VACANT. Design assistant required immediately for company manufacturing prestressed concrete. Knowledge of prestressed concrete design not essential. Write, giving details of qualifications, experience, and salary required, to CHARLTON CONCRETE CO., LTD., 7A Pulteney Street, Bath, Somerset.

SITUATION VACANT. Experienced reinforced concrete detailer-draughtsman required by ROW RIVER CO., LTD. Permanent and progressive post. 36½-hours' week. Superannuation scheme. Salary according to age and experience. Existing holiday arrangements honoured. Telephone Euston 7814.

SITUATION VACANT. Designer-draughtsman required for London office of well-known reinforced concrete engineering contractors. Experience in reinforced concrete frames, floors, roofs, and staircase construction essential. Progressive post, pension scheme, and five-days' week. Write fully, stating salary required, to BOX 4270, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Estimator required by PETER LIND & CO., LTD., Romney House, Tufton Street, Westminster, S.W.1. Candidates must have good all-round experience in civil engineering work, more particularly the design of temporary works such as stagings, cofferdams, etc. Apply in writing only, giving age and full description of experience, and stating salary required.

SITUATIONS VACANT. Detailers experienced in reinforced concrete, preferably with some design knowledge, required for London professional office. Experience of steelwork an advantage but not essential. The work is varied and offers scope for initiative and advancement. The positions are permanent and are particularly suitable for those hoping to gain further experience. Five-days' week. Apply, stating full details, and salary required, to FAHMER & DARK, Romney House, Tufton Street, Westminster, S.W.1.

SITUATION VACANT. Design assistant (general construction) required by East African Railways and Harbours Civil Engineering Department on contract for tour of 36 months in first instance. Consolidated salary up to £1700 a year. Gratuity at rate of 10 per cent. of total salary drawn. Free passages. Liberal leave on full salary. Candidates must be equally experienced in steel and reinforced concrete structural design. Write to the CROWN AGENTS, 4 Millbank, London, S.W.1. State age, name in block letters, full qualifications and experience, and quote MaB/40744/CAR.

SITUATION VACANT. Senior designer required by engineers who specialise in consulting prestressing work. Applicants must be ten years out of Degree, and have had wide experience in a design office working on reinforced and prestressed concrete in a responsible position. Thorough knowledge of methods of analysis of structures and fundamentals of design essential. Preference will be given to applicants with some prestressing research experience, and with sufficient site experience for A.M.I.C.E. Write, stating qualifications, experience, and present salary, to THE PRE-STRESSED CONCRETE CO. LTD., 171 Victoria Street, London, S.W.1.

THE TRUSSED CONCRETE STEEL COMPANY LIMITED

ENGINEERING DEPARTMENT

Applications are invited from Reinforced Concrete Designers and Detailers for work in the Company's Head Office in London (near Waterloo Station), and its Harlow, Birmingham, Glasgow, and Manchester Design Offices. Five-days' week. Pension and Profit Sharing Schemes are in operation. Please apply, giving full details of age, education and previous experience, to the ENGINEERING MANAGER, Truscon House, 35-41 Lower Marsh, London, S.E.1.

(Continued on next page).

MISCELLANEOUS ADVERTISEMENTS.

(Continued from previous page.)

SITUATIONS VACANT. Prestressed concrete engineers required. Should have a minimum of two years' general experience in structural or civil engineering. Must have structural sense and imagination, and be able to think. Permanent men required. Good prospects. Starting salary dependent upon experience and qualifications. Previous prestressing experience not vital. Write, giving full particulars, to **THE PRE-STRESSED CONCRETE CO. LTD.**, 171 Victoria Street, London, S.W.1.

SITUATION VACANT. Senior designer-draughtsman, capable of controlling junior draughtsmen, required for firm of reinforced concrete engineers and contractors in South-West district of London. Applicants should be qualified, and used to preparing calculations and quantities for single- and multi-story buildings. The post is permanent with possible directorship. Salary £800-£1200 according to qualifications and experience. Write full particulars, Box 4290, **CONCRETE AND CONSTRUCTIONAL ENGINEERING**, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Engineer wanted to visit sites and precast concrete works in the United Kingdom to check prestressed concrete construction and to act as liaison between engineer, architect and contractor. The work is similar to that of a consulting engineer's resident engineer, and will involve inspection and reporting, and also development of techniques of prestressing application. There may be a score of sites between Inverness and Southampton to watch at any time. The post carries extensive responsibility, and applicants will need a practical knowledge of prestressing problems and building construction, as well as the wish to move about the country every day. Good salary and prospects for the right man. Travelling expenses paid. Write, giving age, qualifications and experience, to **THE PRE-STRESSED CONCRETE CO. LTD.**, 171 Victoria Street, London, S.W.1.

SITUATIONS VACANT. Consulting reinforced concrete engineers, Westminster, require detailers. Design knowledge preferable but not essential. Details of experience, and salary required, to Box 4291, **CONCRETE AND CONSTRUCTIONAL ENGINEERING**, 14 Dartmouth Street, London, S.W.1.

REINFORCED CONCRETE DETAILERS REQUIRED

Consulting Structural Engineers have two vacancies in their Surrey office for Reinforced Concrete Designer-Detailers. Applicants must be experienced in detailing all types of reinforced concrete structures, and especially multi-storey building frames.

Commencing salaries will range from £700 to £900 per annum, depending on experience and ability. The positions offered are permanent, with excellent prospects for advancement. A Staff Superannuation Scheme is in operation.

Apply, giving age and full details of experience, to Box No. 4273, **CONCRETE AND CONSTRUCTIONAL ENGINEERING**, 14 Dartmouth Street, London, S.W.1.

DIESPEKER & CO. LTD.

have a vacancy for a Chief Designer-Draughtsman. Applicants should be qualified, possess a complete knowledge and wide experience of Reinforced Concrete Frames and of Building Construction, and be capable of controlling a medium-size Drawing Office.

The Post is permanent and pensionable.

Write (in confidence) to

The Secretary,
Clifton House,
Euston Road, N.W.1,

giving full particulars of experience and qualifications, and stating salary required.

THE KLEINE CO. LTD.

*Designers of, and contractors for,
Reinforced Concrete Frame Buildings
and*

*Specialists in Fire-resisting
Hollow-Brick Floors since 1905*

have **VACANCIES** for

REINFORCED CONCRETE

DRAUGHTSMEN

and

DETAILERS

These are PERMANENT POSITIONS offering TOP GRADE SALARIES and exceptional opportunities for advancement. Working conditions, in spacious and well-lighted offices, are excellent, and there is a non-contributory SUPERANNUATION SCHEME in operation.

Applicants are invited to write, giving fullest possible information concerning experience and stating the salary they consider to be a measure of their ability, to:

**The Managing Director,
The Kleine Co. Ltd.,
9/13 George Street,
Manchester Square,
London, W.1**

SITUATIONS VACANT. TWISTELL REINFORCEMENT, LTD., have vacancies for designers and detailers in their London drawing offices. Apply, stating experience, to 43 Upper Grosvenor Street, London, W.1.

SITUATION VACANT. Senior design engineer required for civil engineering and structural design, with special reference to the study of nuclear power station projects. Sound experience of civil engineering works, including reinforced concrete and structural steel, essential. Some experience of conventional power station design desirable. Excellent prospects for the right man capable of supervising drawing office of about 25, and having imagination, willingness to learn, and interest in a new field. Salary according to experience, but in range £1450-£1750. Apply in confidence to TECHNICAL DIRECTOR, c/o Box CCE 800, L.P.E., 55 St. Martin's Lane, London, W.C.2.

SITUATION VACANT. Technical representative with knowledge of concrete products and reinforced concrete design required to cover Scotland. This is a senior position directly responsible to a Director, and applicants must be capable of initiating negotiations at high level. Salary commensurate with qualifications and ability. THE SCOTTISH CONSTRUCTION CO. LTD., Sighthill Industrial Estate, Edinburgh 11.

SITUATIONS VACANT. WATES, LTD., have vacancies for structural engineering assistants for design and detailing of reinforced concrete structures and precast work. Salary according to qualifications. Five-days' week, bonus and pension schemes. Write, stating particulars of age, education, experience, etc., to Wates, Ltd., 1258-60 London Road, Norbury, S.W.16.

SITUATIONS VACANT. Civil engineering department of THE COPPER CO. (G.B.), LTD., 140 Piccadilly, London, W.1, require following staff for varied work on collieries and steelworks, etc.: Experienced reinforced concrete designers; Reinforced concrete detailers; Drawing and schedule checkers; Assistant quantity surveyors. Apply in writing, stating age, experience, and salary required. Pension scheme and five-days' week.

Opportunity for Reinforced Concrete Designers...

to join the London staff of

BRE

There are opportunities for Reinforced Concrete Designers in their New London Office at 54 Grosvenor Street, equipped with controlled heating and ventilation and canteen. Five day week — 37½ hours — Pension Fund. Salaries are reviewed annually.

Designer-Detailers with good experience will be offered salaries of £750 to £950 per annum, and Detailers with some design experience, up to £750 per annum.

We also have a few openings for Student Apprentices of good educational standard and for Students who have just completed the Higher National Certificate Course.

THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD

Chief Engineer: A. F. MARSH, B.Sc., M.I.C.E., M.J.Steel.E., M.A.R.C.E.

M-W 809

LIVERSEDEGE

CONSULTING STRUCTURAL ENGINEERS

require

Designer-detailers and draughtsmen experienced in all types of reinforced concrete work. Structural steelwork experience an advantage. Pleasant conditions, good salaries and prospects for suitable applicants.

Details to

JOHN LIVERSEDEGE & ASSOCIATES

42 Portland Place, London, W.1

SITUATION VACANT. W. & C. FRENCH, LTD., urgently require a detailer. Essential that person selected should be able to detail reinforced concrete structures quickly and accurately from sketch designs or calculations. Write, stating age, experience, and salary requirements, to PERSONNEL MANAGER, 50 Epping New Road, Buckhurst Hill, Essex.

SITUATION VACANT. CENTRAL ELECTRICITY AUTHORITY, Research Laboratories, Leatherhead, require a third assistant engineer (civil) to investigate problems in connection with mix design and testing and application of concrete incorporating fly ash. Candidates should have a degree in civil engineering or equivalent, with some industrial or research experience. Salary £930-£1140 per annum. Applications, stating age, qualifications, experience, present position and salary, to D. MOPPAT, Director of Establishments, Winsley Street, London, W.1, by 23 July, quoting Ref.: CCE/836.

SITUATION VACANT. Assistant engineer, experienced in the design and detailing of reinforced and prestressed concrete structures, required in consulting engineer's office. Salary and profit-sharing bonus commensurate with experience, qualifications, and proven ability. Five-days' week. Apply, giving full particulars, to CHARLES WEISS & PARTNERS, Consulting Engineers, 1 Wandsworth Road, London, S.W.8 (near Vauxhall Bridge).

SITUATIONS VACANT. Senior reinforced concrete and structural steelwork designers required for employment on major projects in South Wales and the Midlands. Salaries plus allowances not less than £1000 per annum. Optional pension scheme and opportunities for promotion. Box 4293, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Designer and detailer in reinforced concrete required, also junior. Pleasant well-lighted offices. Varied work and opportunity to learn. State experience, if any, and salary. A. B. DAILEY, CONSULTING ENGINEER, 175 Lavender Hill, Clapham Junction, London.

J. L. KIER & CO. LTD.

CIVIL ENGINEERING CONTRACTORS

require for their London Office:

(1) Senior reinforced concrete designer for responsible position in the drawing office. Applicants must be fully experienced in the design and detailing of all types of reinforced concrete structures. Practical experience desirable. Good salary.

(2) Draughtsmen with mechanical/structural experience for planning department. Salary according to age and experience. Pension scheme Write, giving details of age and experience, etc., to J. L. KIER & CO., LTD., 7, Lygon Place, Grosvenor Gardens, London, S.W.1.

(Continued on next page.)

MISCELLANEOUS ADVERTISEMENTS.

(Continued from previous page.)

**REINFORCED CONCRETE
DESIGNERS**

DETAILERS & DRAUGHTSMEN

are invited to apply for vacancies in the Keynsham and Bristol offices of Square Grip Reinforcement Co., Ltd., Keynsham, Bristol. Opportunity to work on variety of structures: Five-days' week, modern offices. Previous experience essential for senior posts, but consideration given to other suitable draughtsmen. Good salaries with pension and profit-sharing schemes.

SITUATION VACANT. British Railways, Chief Civil Engineer's office, Paddington Station. Draughtsman experienced in design of reinforced and prestressed concrete bridges and structures. Post offers permanency after probationary period, with membership of superannuation fund. The salary for this post commences at £770 and rises to £835 per annum after four years. Certain free and privilege ticket facilities on British and Continental Railway systems. Apply to CHIEF CIVIL ENGINEER, Paddington Station, London, W.2.

SITUATION VACANT. Engineering assistant (structural) required by Northern Rhodesia Government on contract for four or three years. Consolidated salary, according to experience, in scale £905 to £1200 a year. Gratuity at rate of £100-£150 a year. Outfit allowance £30. Free passages. Liberal leave on full salary. Candidates should be under 35 years of age, have served a four-years' apprenticeship to a structural engineer, and have had experience of design and preparation of working drawings of reinforced concrete structures. Knowledge of structural steelwork an advantage. Write to the CROWN AGENTS, 4 Millbank, London, S.W.1. State age, name in block letters, full qualifications and experience, and quote M2B/41247/CAR.

DOW-MAC PRODUCTS LTD.

Require

SIX DESIGNERS

EXPERIENCED IN

**PRESTRESSED, PRECAST, OR REINFORCED
CONCRETE.**

Terms of Employment:

1. Salary up to £1200 per annum, dependent upon qualifications.
2. Pension Scheme.
3. Removal expenses paid.
4. One month's settling-in allowance.
5. Employment contract will follow three months' probationary period, if required.

Write, giving full details, to Staff Manager, Dow-Mac Products, Ltd., Tallington, Stamford, Lincolnshire.

FOR SALE.

FOR SALE. Steel tubes and fittings, sections, strips, blanks, etc. E. STEPHENS & SON, Ltd., Bath Street, London, E.C.1. Clerkenwell 1731.

FOR SALE. Approximately 50 tons of high tensile steel rods of various diameters, mostly about $\frac{1}{2}$ in. Also large tonnage of EN 8 steel, flat and square bars, in small and medium sections. WOODFIELD & TURNER LTD., Burnley. Telephone: 78134.

FOR HIRE.

FOR HIRE. Lattice steel erection masts (light and heavy), 30 ft. to 150 ft. high, for immediate hire. BELL-MAN'S, 21 Hobart House, Grosvenor Place, London, S.W.1.

**DATA FOR PRICING
REINFORCED CONCRETE.**

Materials.

(Delivered in London area.)

AGGREGATES (per cu. yd.).—Washed sand, 25s. 1d. Clean shingle: $\frac{3}{4}$ in., 21s. 5d.; $\frac{1}{2}$ in., 24s. Pit ballast, 24s. 6d.

CEMENT (per ton, delivered at Charing Cross).—Portland cement, 6 tons and upwards, 104s. 6d. 1 ton to 6 tons, 116s. 6d. Paper bags and non-returnable jute sacks included.

Rapid-hardening Portland, 10s. 6d. above ordinary Portland.

Aquacrete and 417, 32s. 6d. above ordinary Portland; paper bags included.

Colorecrete (buff, red, and khaki), in 6-ton loads, 161s.; paper bags included.

Snowcrete, 265s., inc. paper bags.

"Super-Cement", 32s. 6d. per ton above ordinary Portland cement; paper bags included.

High-alumina cement: per ton, 314s. 6d.; 2 tons, at 304s. 3d.; 4 tons, at 299s. 3d.; 6 tons, at 295s. 9d.

Snowcem paint, 71s. per cwt. including containers.

SHUTTERING.—1" and $1\frac{1}{2}$ " deal sawn shuttering boards, £95-£100 per standard.

REINFORCEMENT.—Mild steel bars, B.S. 785 (per cwt.); $\frac{1}{2}$ in. to 2 $\frac{1}{2}$ in., 45s. 9d.; $\frac{3}{4}$ in. to $1\frac{1}{2}$ in., 47s. 6d.; $\frac{1}{2}$ in., 48s. 3d.; $\frac{3}{4}$ in., 49s. 9d.

Materials and Labour.

(Contracts up to £5000. Including 10 per cent. profit.)

PORTLAND CEMENT CONCRETE, 1:2:4.—

Foundations, 2s. 7 $\frac{1}{2}$ d. per cu. ft. Columns, 3s. 6 $\frac{1}{2}$ d. per cu. ft. Beams, 3s. 3 $\frac{1}{2}$ d. per cu. ft. Floor slabs, 4 in. thick, 9s. 4 $\frac{1}{2}$ d. per sq. yd.; Do., 5 in., 11s. 10d.; Do., 6 in., 13s. 6d.; Do., 7 in., 15s. 10 $\frac{1}{2}$ d. Walls 6 in. thick, 15s. per sq. yd. Add for hoisting above ground level, 3s. 9 $\frac{1}{2}$ d. per cu. yd. Add for rapid-hardening Portland cement, 3s. per cu. yd.

REINFORCEMENT.—Mild steel bars (B.S. 785), including cutting, bending, fixing, and wire (per cwt.).— $\frac{1}{2}$ in. to $\frac{3}{4}$ in., 79s. 3d. $\frac{1}{2}$ in. to $\frac{1}{2}$ in., 72s. 10d. $\frac{3}{4}$ in. to 2 $\frac{1}{2}$ in., 66s. 10d.

SHUTTERING AND SUPPORTS.—

Walls, 214s. 2d. per square.

Floors (average 10 ft. high), 198s. 6d. per square. In small quantities, 2s. 7 $\frac{1}{2}$ d. per sq. ft.

Columns, average 18 in. by 18 in. (per sq. ft.), 3s.; in narrow widths, 3s. 10d.

Beam sides and soffits, average 9 in. by 12 in. (per sq. ft.), 2s. 11 $\frac{1}{2}$ d.; in narrow widths, 3s. 5 $\frac{1}{2}$ d.

Raking, cutting, and waste, 6 $\frac{1}{2}$ d. per lin. ft.

Labour on splays, 3 $\frac{1}{2}$ d. per lin. ft.

Small fillets to form chamfers, 6 $\frac{1}{2}$ d. per lin. ft.

Wages.

The rate of wages on which the above prices are based are: Carpenters and joiners, 4s. 1 $\frac{1}{2}$ d. per hour (carpenters 2d. a day tool money); Labourers, 3s. 7d.; Men on mixers and hoists, 3s. 10d.; Bar-benders, 3s. 10 $\frac{1}{2}$ d.

This column is specially compiled for "Concrete and Constructional Engineering," and is strictly copy-right.

STONE COURT AGGREGATES



General View of Plant at Rickmansworth.

ONE OF OUR MODERN CONCRETE AGGREGATES PLANTS

First-Class Washed graded concrete aggregates, and shingles for road dressing, coupled with efficient delivery, are at the service of contractors and Municipal Authorities in London, Berks, Bucks, Herts, and Middlesex Areas.

Our products include Washed Sharp Sand, all sizes of shingles, from $3/16"$ up to $2"$, either crushed or natural.

Special Specifications made to order.




STONE COURT BALLAST CO. LTD.
PORTLAND HOUSE, TOTHILL ST., WESTMINSTER, S.W.1

Telephone: Abbey 3456.



Blue Circle
Sulphate Resisting Cement
is now known as
SULFACRETE



The Blue Circle group which spends £250,000 per year on research into the manufacture of cement and its allied products, has made and sold its Sulphate Resisting Cement for the past eight years.

The new trade name of Sulfacrete, the blue bag and the Blue Circle symbol are your safeguards of quality backed by research and practical tests, extending over many years, on concrete placed in soils containing aggressive sulphates.

SULFACRETE

**FORMERLY KNOWN AS BLUE CIRCLE
SULPHATE RESISTING CEMENT**

Supplied by
THE CEMENT MARKETING COMPANY LTD.,
Portland House, Tothill Street, London, S.W.1.
G. & T. EARLE LTD., HULL
THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD.,
Penarth, Glam.